



South Bay Salt Pond Restoration Project



A San Francisco Bay project provided by
the California Department of Fish & Game,
Coastal Conservancy and
U.S. Fish & Wildlife Service

URBAN LEVEE FLOOD MANAGEMENT REQUIREMENTS

DRAFT
(March 2004)



MOFFATT & NICHOL
ENGINEERS

**URBAN LEVEE FLOOD MANAGEMENT REQUIREMENTS
SOUTH BAY SALT POND RESTORATION PROJECT**

Prepared For :

CALIFORNIA STATE COASTAL CONSERVANCY

1330 Broadway, Ste 1100
Oakland, CA 94612

Prepared By :

MOFFATT & NICHOL ENGINEERS

2001 North Main Street, Suite 360
Walnut Creek, CA 94596

March 2004

M&N Job 5196-04

March 24, 2004

Ms. Amy Hutzell
California State Coastal Conservancy
1330 Broadway, 11th Floor
Oakland, CA 94612-2530

Subj: Draft Report – Urban Levee Flood Management Requirements
South Bay Salt Ponds Restoration Project
State Coastal Conservancy Contract No: 02-169
M&N File No: 5196-04

Dear Ms. Hutzell:

We are pleased to provide you with this Draft Report for evaluating levee flood management requirements for the South Bay Salt Ponds Restoration Project. These services were conducted under our flood management and related engineering issues contract.

We have included 4 copies of the report, with electronic copies in a separate submittal.

Should you have any questions or comments on this report, please call me at your convenience.

Sincerely,

MOFFATT & NICHOL ENGINEERS



Dilip Trivedi, Dr. Eng., P.E.
Project Manager

Encl.

CONTENTS

CONTENTS	i
TABLES	iii
FIGURES	iv
GLOSSARY	vi
ABBREVIATIONS	viii
1 INTRODUCTION	1-1
1.1 Background And Purpose	1-1
1.2 Scope Of Work	1-1
2 FLOOD PROTECTION REQUIREMENTS	2-1
2.1 Historical Background	2-1
2.2 US Army Corps of Engineers (USACE)	2-1
2.2.1 General Standards	2-1
2.2.2 Coastal Flood Protection	2-2
2.2.3 Fluvial Flood Protection	2-3
2.2.4 Riverine Levee Certification	2-3
2.2.5 Other Standards	2-4
2.3 Federal Emergency Management Agency (FEMA)	2-4
2.3.1 General Standards	2-5
2.3.2 Coastal Flood Protection	2-6
2.3.3 Riverine/Fluvial Flood Protection	2-6
2.4 Summary And Applicability To SBSP Project	2-6
3 EXISTING LEVEE ASSESSMENT	3-1
3.1 Approach	3-1
3.2 Existing Levees – Physical Conditions	3-2
3.2.1 Construction Method for Existing Levees	3-2
3.2.2 Available Geotechnical Data	3-3
3.2.3 Subsurface Conditions	3-4
3.2.4 Seismicity and Liquefaction	3-4
3.3 Alviso Complex	3-5
3.3.1 Existing Flooding	3-5
3.3.2 Physical Setting	3-7
3.4 West Bay Complex	3-9
3.4.1 Existing Flooding	3-9
3.4.2 Physical Setting	3-10
3.5 Baumberg Complex	3-11
3.5.1 Existing Flooding	3-11

3.5.2	Physical Setting	3-12
4	PROPOSED LEVEE IMPROVEMENTS	4-1
4.1	Design Assumptions	4-1
4.2	Anticipated Post-Project Hydrodynamics.....	4-2
4.3	Geotechnical Assessment	4-2
4.3.1	Assumed Soil Properties for Settlement and Slope Stability Analyses ..	4-2
4.3.2	Assumed Levee Profiles For Settlement and Slope Stability Analyses .	4-3
4.3.3	Settlement and Slope Stability Analysis.....	4-3
4.3.4	Levee Construction Issues.....	4-4
4.3.5	Geotechnical Discussion and Conclusions	4-5
4.4	Design and Cost Estimate	4-5
4.4.1	Alviso Complex	4-5
4.4.2	West Bay Complex	4-6
4.4.3	Baumberg Complex	4-6
4.5	Items For Further Study	4-6
5	REFERENCES.....	5-1
	APPENDICES	A
A.	Survey Data	A
B.	Field Data Forms.....	B
C.	Pond Elevations	C

TABLES

Table

FIGURES

1.1a	Location Map - Alviso Complex (1)
1.1b	Location Map - Alviso Complex (2)
1.1c	Location Map - Alviso Complex (3)
1.1d	Location Map - West Bay Complex
1.1e	Location Map - Baumberg Complex
2.2.2	U.S. Army Corps of Engineers Freeboard Requirements
2.2.4	Levee Certification Decision Tree
2.3.2	Federal Emergency Management Agency (FEMA) Freeboard Requirements
3.2.2a	Location of Borings – Alviso Complex (1)
3.2.2b	Location of Borings – Alviso Complex (2)
3.2.2c	Location of Borings – West Bay Complex
3.2.3a	Land Subsidence In Santa Clara Valley (1934 – 1967)
3.2.3b	Land Subsidence and Depth to Groundwater In San Jose (1910 – 1995)
3.3.1a	100-year Floodplain – Alviso Complex (1)
3.3.1b	100-year Floodplain – Alviso Complex (2)
3.3.2a	Alviso Complex, Pond A1 Aerial Photo
3.3.2b	Alviso Complex, Pond A1 Photo & Cross Section
3.3.2c	Alviso Complex, Pond A2W Aerial Photo
3.3.2d	Alviso Complex, Pond A2W Photo & Cross Section
3.3.2e	Alviso Complex, Pond A2E, Pond B2 Aerial Photo
3.3.2f	Alviso Complex, Pond A2E Photo & Cross Section
3.3.2g	Alviso Complex, Pond A3W Aerial Photo
3.3.2h	Alviso Complex, Pond A3W Photo & Cross Section
3.3.2i	Alviso Complex, Oxidation Ponds Aerial Photo
3.3.2j	Alviso Complex, Pond A4 Aerial Photo
3.3.2k	Alviso Complex, Pond A4 Photos & Cross Section
3.3.2l	Alviso Complex, Pond A8 Aerial Photo
3.3.2m	Alviso Complex, Pond A8, New Chicago Marsh Aerial Photo

Figures (continued)

3.3.2n	Alviso Complex, New Chicago Marsh Aerial Photo
3.3.2o	Alviso Complex, New Chicago Marsh Photos
3.3.2p	Alviso Complex, Pond A22 Aerial Photo
3.3.2q	Alviso Complex, Pond A22 Photo & Cross Section
3.4.1	100-year Floodplain – West Bay Complex
3.4.2a	West Bay Complex, Ponds S5 and 3 Aerial Photo
3.4.2b	West Bay Complex, Pond S5 Photo & Cross Section
3.4.2c	West Bay Complex, Ponds 3, SF2 Aerial Photo
3.4.2d	West Bay Complex, Pond 3 Photo & Cross Section
3.4.2e	West Bay Complex, Ponds 2, SF2 Aerial Photo
3.5.1	100-year Floodplain – Baumberg Complex
3.5.2a	Baumberg Complex – Site Features
3.5.2b	Baumberg Complex – Levee Cross Sections
4.3.3a - 4.3.3j	Alviso Complex – Slope Stability & Settlement Analysis
4.3.3k - 4.3.3m	West Bay Complex – Slope Stability & Settlement Analysis
4.3.3n	Stability Analysis Charts, Shear Strength = 200 psf
4.3.3o	Stability Analysis Charts, Shear Strength = 400 psf
4.4.1	Alviso Complex, Proposed Typical Section, A1, A2W
4.4.2	Alviso Complex, Proposed Typical Section, A2E, A3W
4.4.3	West Bay Complex, Proposed Typical Section

GLOSSARY

100-year flood	The one-percent annual chance flood. The one-percent annual flood is the flood that has a one-percent chance of being equaled or exceeded in any given year. [†]
Base Flood	The flood which has “regulatory significance”. Generally it is considered synonymous with the flood having a one-percent chance of being equaled or exceeded in any given year. [‡]
Coastal Flooding	Flooding that occurs along the Great Lakes, the Atlantic and Pacific Oceans, the Gulf of Mexico, and other estuarine coastlines. [†]
Coastal High Hazard Areas	Special Flood Hazard Areas along the coasts that have additional hazards due to wind and wave action. These areas are identified on Flood Insurance Rate Maps as Zones V, V1-V30, and VE. [‡]
Flood	A general and temporary condition of partial or complete inundation of normally dry land areas from (1) the overflow of inland or tidal waters or (2) the unusual and rapid accumulation or runoff of surface waters from any source. [†]
Flood Hazard Factor	The average weighted difference between the 10- and 100-year water surface elevations rounded to the nearest one-half foot, multiplied by 10, and shown as a three-digit code. [†]
Flood Insurance Rate Map	Official map of a community on which the Mitigation Division Administrator has delineated both the special hazard areas and the risk premium zones applicable to the community. [‡]
Floodplain	Any land area susceptible to being inundated by flood waters from any source. [‡]
Freeboard	An addition to a levee’s design height to ensure against overtopping during the design flood.*
Hydraulic Analysis	An engineering analysis of a flooding source carried out to provide estimates of the elevations of floods of selected recurrence intervals. [†]
Hydrologic Analysis	An engineering analysis of a flooding source carried out to establish peak flood discharges and their frequencies of occurrence. [†]
Levee	A manmade structure, usually an earthen embankment, designed and constructed in accordance with sound engineering practices to contain, control, or divert the flow of water so as to provide protection

[†] Glossary of Terms, “Guidelines and Specifications for Flood Hazard Mapping Partners [April 2003]”, FEMA, http://www.fema.gov/pdf/fhm/fhm_gsgl.pdf

[‡] NFIP Definitions, FEMA website <http://www.fema.gov/nfip/19def2.shtm>

* Appendix A, “Risk Analysis and Uncertainty in Flood Damage Reduction Studies”, National Research Council, 2000

¹ Flood Insurance Study, City of San Jose, California, Volume 1, FEMA, 1998, p. 62

	from temporary flooding. [†]
Riverine/Fluvial Flooding	The overbank flooding of rivers and streams. [†]
Special Flood Hazard Area	The area delineated on a National Flood Insurance Program map as being subject to inundation by the base flood. SFHAs are determined using statistical analyses of records of riverflow, storm tides, and rainfall; information obtained through consultation with a community; floodplain topographic surveys; and hydrologic and hydraulic analyses. [†]
Stillwater Flood Elevation	Projected elevation that flood waters would assume in the absence of waves resulting from wind or seismic effects. [†]
Urban Levee	Levees that provide protection from flooding in communities, including their industrial, commercial, and residential facilities.*

[†] Glossary of Terms, FEMA

* EM 1110-2-1913, "Design and Construction of Levees", US Army Corps of Engineers, April 30, 2000, p.1-2

ABBREVIATIONS

ACFCWCD	Alameda County Flood Control and Water Conservation District
BFE	Base Flood Elevation
CFS	cubic feet per second
FEMA	Federal Emergency Management Agency
FHF	Flood Hazard Factor
FIRM	Flood Insurance Rate Map
GIS	Geographic Information System
HOWL	Highest Observed Water Level
LOWL	Lowest Observed Water Level
MHHW	Mean Higher High Water
MHW	Mean High Water
MLLW	Mean Lower Low Water
MLW	Mean Low Water
MSL	Mean Sea Level (incorrectly used as NGVD frequently)
MTL	Mean Tide Level
NFIP	National Flood Insurance Program
NGVD	National Geodetic Vertical Datum, 1929
NOAA	National Oceanic and Atmospheric Administration
NOS	National Ocean Service
SCVWD	Santa Clara Valley Water District
SFHA	Special Flood Hazard Area
SFRWQCB	San Francisco Regional Water Quality Control Board
USACE	United States Army Corps of Engineers
WSEL	Water Surface Elevation

1 INTRODUCTION

1.1 BACKGROUND AND PURPOSE

The South Bay Salt Ponds Restoration Project consists of enhancing the recently acquired Cargill Salt Ponds, which have been grouped into the following pond complexes:

- Alviso Complex - The 7500-acre complex of ponds between Charleston Slough and Mud Slough in Santa Clara and Alameda Counties, which consists of seven smaller groups of ponds separated by streams. The Alviso complex is shown in Figures 1.1a through 1.1c.
- West Bay Complex - The 1500-acre complex of ponds in southern San Mateo County, which consists of three smaller groups of ponds separated by Hwy 84 and Ravenswood Slough. The West Bay complex is shown in Figure 1.1d.
- Baumberg Complex - The 4800-acre complex of ponds between Hwy 92 and Coyote Hills Slough in Alameda County, which consists of three smaller groups of ponds separated by streams. The Baumberg complex is shown in Figure 1.1e.

Work described in this report was conducted for the California Coastal Conservancy, as part of the data acquisition phase of the restoration project. This report is intended to identify, at a conceptual engineering level, the flood management requirements for the inboard salt pond levees which could function as perimeter (Bayfront) levees after implementation of the proposed restoration project. In addition, it includes a conceptual feasibility analysis which addresses levee improvements and parametric cost estimates that could be used for planning a continuous perimeter flood protection barrier for urban communities.

Prior studies have addressed potential interactions between the restoration project and water conveyance facilities (M&N 2003). The M&N report discussed the possible effects of restoration on San Francisco Bay and on the flood conveyance characteristics of local creeks, rivers, and flood control channels due to reestablishing hydraulic connections to the Bay.

With the expected range of effects in flooding characteristics, an important planning consideration is the preservation or improvement of existing flood protection levels for local communities. The salt ponds currently provide a varying, but substantial, level of flood protection at the bayfront levees fronting the Bay. During the planning phase of the restoration project, and potentially into the future, these levees will not be maintained which transfers flood protection functions to the urban levees that currently function primarily as salt pond perimeter levees.

1.2 SCOPE OF WORK

The scope of work included the following:

Task A - Determine Criteria and Standards For Flood Control Levees

This task included review of existing codes and literature and discussions with local flood control districts to determine the flood control standards that will apply to perimeter levees in the South Bay.

Task B – Urban Levee Condition Report

This task included evaluating the existing urban levees for the purpose of developing a conceptual engineering feasibility study. The following subtasks were performed:

- Identify Urban Levee Segments
- Gather Existing Data
- Additional Field Data – This subtask includes a survey of the existing urban levee crest centerline and establishment of benchmarks for future use.
- Reconnaissance Level Geotechnical Assessment - This subtask includes a field investigation to characterize the existing conditions of the salt pond levees and to identify deficiencies in the urban levees to meet the flood protection requirements as a result of the restoration project.

Task C - Develop Scope For Subsequent Geotechnical Assessment (Provided Separately)

This task included preparing a scope of work for an initial geotechnical assessment of the condition of the urban levees in the project area. The scope of work included a description of required field investigation techniques and equipment type, access requirements, limits and extent of geotechnical sampling, laboratory testing to be performed, and preliminary level costs to conduct the investigation.

Task D - Assess Feasibility Of Providing Continuous Flood Protection Levee

This task included an engineering feasibility analysis to provide continuous flood protection using selected urban levee segments. Each levee segment identified as a potential flood protection levee will be addressed separately, to assist in the environmental documentation process

Since the flood level and the required levee crest elevation will depend on the restoration alternative selected, a range of water levels was assumed for cost estimates. The improvement concepts and costs could be used in preparing alternatives for environmental documentation.

Task E - Provide Information For GIS (Provided Separately)

In anticipation of a GIS system to be developed by others, this task includes providing a GIS layer(s) for existing the urban levee that will include topographic data and will identify the future flood protection levees alignment.

2 FLOOD PROTECTION REQUIREMENTS

This report focuses on the improvement of the urban levees between the salt ponds and upland communities. For purposes of this report, the urban levee is defined as the salt pond levee which “directly” protects (or will protect after restoration) a community from tidal flooding. In most cases it is not the present Bayfront or Interior (between 2 adjacent ponds) levee, but represents a “last line of defense” against tidal and fluvial flooding. As a common means to reduce flood damage, the construction of levees can also result in revision of floodplain limits and relieve a community from the cost of purchasing federally mandated flood insurance policies. The following sections describe levee design and construction standards that apply to the restoration project.

2.1 HISTORICAL BACKGROUND

The federal government has been involved in flood control since the creation of the U.S. Army Corps of Engineers (USACE) in 1802, and has been explicitly responsible for flood control since the Flood Control Act of 1936. Construction of levees has been an important component of flood control, and over the years the USACE has developed standard levee design methods and criteria for the purpose of providing a uniform level of flood protection.

The 1968 National Flood Insurance Act and the 1973 Flood Disaster Protection Act created and revised the National Flood Insurance Program (NFIP) which sought to accomplish two primary goals:

“Congress wanted property owners to purchase flood insurance to (1) provide them with financial relief should they suffer losses in a flood and (2) lessen the financial burden on federal, state, and local governments to provide grants and low-interest loans to cover the losses of uninsured property owners. These acts also sought to reduce damage from moderate-sized floods by encouraging construction of levees and other flood damage reduction structures.” (National Research Council 2000)

In 1979, the Federal Emergency Management Agency (FEMA) was created to consolidate numerous government agencies into a less complex, centralized agency. FEMA was given responsibility for administration of the NFIP, and adopted USACE flood control standards for certification of levees.

The following sections describe the role of the federal agencies in flood protection, their standards and methods, and the resulting levee certification requirements for the restoration project.

2.2 US ARMY CORPS OF ENGINEERS (USACE)

The USACE provides financial resources, design services, and construction support for various projects designed to improve existing flood protection levels. The USACE also has FEMA-authorized authority to certify that a levee provides 100-year flood protection (Federal Register, 44 CFR Part 65.10e).

2.2.1 General Standards

Flood control standards have been developed to protect communities from various types of flooding. The project area is subject to two main flooding types: coastal flooding and fluvial flooding. Coastal flooding can occur due to high tides in the Bay exceeding the ground elevations or overtopping levees. These tidal flooding events are a result of a combination of astronomical (tidal), atmospheric (low pressure), and local (wind/wave) effects. Fluvial

flooding can result from high water levels in waterways during extreme rainfall events, overtopping riverbanks, levees, or floodwalls.

Through the USACE's extensive experience with levees has emerged an acknowledgement of the need for engineering judgement in developing design criteria:

"Numerous factors must be considered in levee design. These factors may vary from project to project, and no specific step-by-step procedure covering details of a particular project can be established. However, it is possible to present general, logical steps based on successful past projects that can be followed in levee design and can be used as a base for developing more specific procedures for any particular project." (USACE 2000)

100-Year WSEL

The 100-year WSEL is the elevation of the flood with a one-percent chance of exceedance during a single year. This elevation is a site-specific elevation based on existing topography and hydraulic modeling, and typically increases in elevation with increasing distance from the receiving waterbody.

The 100-year WSEL can be based on coastal or fluvial flooding, or a combination of the two. Coastal flooding can be estimated by collecting data on tides, winds, shore geometry, and other data, and comparing with existing ground elevations. Fluvial flooding can be estimated by performing a hydrologic/hydraulic analysis of the waterway based on rainfall data, channel geometry, and other factors.

2.2.2 Coastal Flood Protection

The USACE's approach to coastal levees in the Bay has been described in the San Francisco Bay Shoreline Study (USACE 1988), and can be summarized as follows:

"The design crest elevations for the levees and other protective structures considered in this study were based on four components: "still-water" tide elevations; tidal flood elevations; wave run-up elevations; and freeboard. An allowance for overbuild above the design crest elevations of levees was made to compensate for post-construction settlement."

For outboard (nearest to the Bay) coastal levees exposed to wind-induced waves, the crest elevation requires 1 foot of freeboard above the wave run-up elevation. For outboard coastal levees not exposed to wind-induced waves and for inboard (landward of the outboard levee) coastal levees, the crest elevation requires 1 foot of freeboard above the still-water tide elevation. Figure 2.2.2 shows these freeboard requirements.

Wave effects were not included for the inboard levees due to the presence of the outboard levee; however, the USACE acknowledged the following:

"If an existing outboard levee were severely eroded or breached, the actual water surface elevation at the inboard project levee would approach or equal the tide elevation in the open bay, which could significantly exceed the design water surface elevation.....

..... Because additional freeboard was included in the crest elevations of the inboard project levees in response to the threat of failure of the existing outboard levees, no height was added to the inboard levees to address the small amount of wave run-up expected. Although this design could result in wave overtopping of the inboard levees under worst-case conditions (i.e., failure of the outboard levees in combination with severe winds during the peak of an extreme high tide), the volume of overtopping is expected to be minor even under those conditions."

For a tidal restoration project, breaching of an existing outboard levee will occur in one of two ways: 1) immediately, as part of the restoration, to restore tidal influence to a specific area; or 2) slowly, as erosion effects are coupled with a lack of maintenance, possibly over a period of years. In both cases the inboard levees will be exposed to tidal waters and perhaps wind-wave action, requiring that wave run-up and erosion be considered in the analysis.

It is important to note that the potential of levee overtopping (where permissible) mentioned above highlights the use of site-specific engineering judgement by the USACE. Engineering design criteria for determining the levee crest elevation could thus differ from past or adjacent projects.

2.2.3 Fluvial Flood Protection

The USACE set the original standards for riverine levees as the design flood elevation plus 3 feet of freeboard, which became the widely accepted industry standard:

“The best estimate has traditionally been based on the expected height of a design flood (e.g., a 100-year flood, the magnitude of which has a 1 percent chance of being equaled or exceeded in any given year, and which is here called the “1% flood”). Freeboard was then added above the expected height. Many Corps flood damage reduction projects used a standard of 3 feet of freeboard. “Three feet of freeboard” became an engineering tradition within the Corps and was employed in hundreds of Corps flood damage reduction studies and projects.” (National Research Council, 2000)

This standard was used and continues to be used for FEMA certification. However, the relatively recent development of advanced hydraulic modeling techniques has caused the use of freeboard to be eliminated:

“The 3-feet-of-freeboard concept was used as a design parameter to account for uncertainties associated with hydrologic and hydraulic analysis (Huffman and Eiker, 1991). If these uncertainties were accounted for, exceptions to the 3-feet-of-freeboard requirement were granted.” (National Research Council, 2000)

The uncertainties mentioned have been accounted for in the USACE’s current risk-based analysis approach, which establishes the 100-year WSEL with a high degree of reliability and eliminates freeboard. The 100-year WSEL corresponds with the median one-percent event; that is, an elevation with a 50% chance of non-exceedance during a 1% chance annual event (USACE 1996). This higher reliability is very evident in fluvial systems which have a long flow record (for example, rivers such as Mississippi, Colorado, Sacramento, Sacramento, etc.)

As the USACE adopted this new analysis approach, concerns arose over the non-uniformity of flood protection due to the differences between USACE design methodology and the traditional methods used by FEMA. The following section describes the current status of levee certification by the USACE.

2.2.4 Riverine Levee Certification

Given the FEMA differences between the FEMA and USACE methods, an agreement was reached that allows the USACE to certify levees meeting one of three criteria:

No risk-based analysis performed – Use standard FEMA criteria

Use standard criteria of BFE (1% flood) plus 3 feet of freeboard.

Risk-based analysis performed – Use one of the following criteria

If the standard FEMA criteria elevation results in a conditional non-exceedance probability of **less than 90%** passing the 1% flood, the minimum levee elevation will be brought up to the elevation corresponding to a 90% chance of non-exceedance.

If the standard FEMA criteria elevation results in a conditional non-exceedance probability of **greater than 95%** passing the 1% flood, the minimum levee elevation can be brought down to the elevation corresponding to a 95% chance of standard FEMA criteria.

If the standard FEMA criteria elevation results in a conditional non-exceedance probability of **between 90% and 95%** passing the 1% flood, the minimum levee elevation can correspond to the standard FEMA criteria.

This certification framework provides integration of the two divergent design methodologies used by the USACE and FEMA. Figure 2.2.4 shows a levee certification decision tree graphically depicting this framework.

2.2.5 Other Standards

- The USACE has adopted minimum Factors of Safety (FS) for Static and Dynamic Geotechnical Stability. These standards apply to different time periods, durations, and loading conditions as follows:
- Case I – End of construction, FS = 1.3
- Case II – Sudden Drawdown, FS = 1.0 to 1.2
- Case III – Steady seepage from full flood stage, FS = 1.4
- Case IV – Earthquake, conduct standard and site specific studies including seismic analysis for all locations in seismic zones 3 and 4, and those locations in zone 2 where potential for liquefaction exists (USACE 1995)

2.3 FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA)

Among many responsibilities, FEMA sets federal flood management standards, including determination of areas that are in the 100-year floodplain (coastal, fluvial or combination of both). These areas are identified on the Flood Insurance Rate Maps (FIRMs) as Special Flood Hazard Areas (SFHA), and properties within the SFHA are subject to several requirements:

- all federally-backed loans must be protected by flood insurance (most lenders require this whether federal or not);
- all new or substantially improved structures must have the lowest floor elevated above the BFE.

Areas which are designated as SFHA are lower than the BFE and are not protected by a FEMA certified levee. If a non-certified levee fronts an urban development or community, a Flood Hazard Factor (FHF), which is a measure of the flooding risk and extent of potential flooding of the community, is usually determined by FEMA. The SFHA are shown on the FIRMs as zones that start with the letter A or V:

- Zone A – base flood elevation (BFE) and flood hazard factor (FHF) not determined;
- Zone AO – sheet flooding from 1 to 3 feet deep, no FHF determined;

- Zone AH – BFE shown, flooding from 1 to 3 feet deep, no FHF determined;
- Zone AE – BFE shown, depth will vary based on ground elevation, no FHF determined;
- Zone A1-30 – BFE and FHF determined, subdivided by FHF;
- Zone V – coastal flooding areas subject to 3-foot high wave action or greater, no BFE or FHF determined;
- Zone VE – coastal flooding areas subject to 3-foot high wave action or greater, BFE determined, no FHF determined;
- Zone V1-30 – coastal flooding areas subject to 3-foot high wave action or greater, BFE and FHF determined.

Additionally, properties outside of the SFHA but within the 500-year floodplain are defined on the FIRM's as either Zone B or Zone X and are not subject to the SFHA requirements. However, voluntary flood insurance for these zones is available at lower premiums than that for properties within the 100-year floodplain.

Although flooding can be divided into two main categories, coastal flooding and fluvial flooding, estuarine areas will in most cases be exposed to a combination of both types of flooding. Coastal flooding can occur due to high tides in the Bay exceeding the ground elevations or waves overtopping the levees. These tidal flooding events are a result of a combination of astronomical (tidal), atmospheric (low pressure), and local (wind/wave) effects. Fluvial flooding can result from high water levels in waterways during extreme rainfall events, overtopping riverbanks, levees, or floodwalls.

As previously stated, this report focuses on the improvement of the urban levees between the salt ponds and the upland communities. As a common means to reduce flood damages, the construction of levees that are certified by FEMA can also result in revision of floodplain limits and relieve a community from current levels of flood risk, and in most cases from the cost of purchasing federally mandated flood insurance policies. The following sections describe levee design and construction standards that have been adopted by FEMA.

2.3.1 General Standards

The Base Flood Elevation (BFE) is the FEMA equivalent of the USACE 100-year WSEL, and is similarly dependent on whether the flooding is coastal or fluvial. Where determined, the BFE is shown on the FIRM. The BFE can be shown as a single elevation for a region, or can be a typical depth over a specified area, or can be shown with contours where the BFE is more variable.

A freeboard is required by FEMA for levee certification. Similar to the determination of the BFE, the amount of freeboard depends on whether the flooding is coastal or fluvial.

Levee Certification Procedure - Because the certification of a levee effectively revises the floodplain, FEMA requires the submission of application forms entitled "Revisions to NFIP Map, MT-2". The MT-2 package contains forms designed to attest to the levee's adequacy, and to ensure that :

- the data and methodology are based on current conditions;
- qualified professionals have assembled data and performed all necessary computations;

- all individuals and organizations affected by proposed changes are aware of the changes and will have an opportunity to comment on them.

The forms require adequate proof that proper levee analysis, design, and construction were performed before revising the floodplain. The standards adopted by FEMA are described in the following sections.

2.3.2 Coastal Flood Protection

For coastal flood protection, the freeboard “must be established at 1 foot above the height of the one percent wave or the maximum wave runup (whichever is greater) associated with the 100-year stillwater surge elevation at the site.” (Federal Register, 44CFR Part 65). Lesser freeboard requirements may be approved if supported with appropriate analysis, but freeboard must be established at a minimum height of 2 feet above the 100-year stillwater surge elevation. Figure 2.3.2 shows these freeboard requirements.

The 100-year stillwater surge elevation incorporates two components of the expected water surface elevation: the *stillwater elevation* is the water elevation based on tides and atmospheric conditions; when adding wind/wave effects the elevation is defined as the *stillwater surge elevation*.

Stillwater surge elevations are determined through coastal engineering analysis (wave hindcasting and forecasting techniques) taking into account various parameters, including bathymetry, water levels, wind speed and direction, and fetch length.

2.3.3 Riverine/Fluvial Flood Protection

Water surface elevations from fluvial flooding are determined by hydraulic modeling based on rainfall and waterway characteristics. The modeling results are typically shown as a longitudinal profile along the waterway due to the variation of water surface elevations with distance from the mouth.

To certify a riverine levee as providing 100-year protection, FEMA has historically required the levees to meet the following design criteria:

- 3 feet of freeboard above the base flood elevation (BFE). Additional freeboard is required within 100 feet of structures/constrictions and at the upstream levee limit (which is tapered out over the length of the levee).
- Geotechnically stable, including foundation stability, prevention of seepage, settlement and erosion which lowers levee stability;

A maintenance and operation plan adopted by and under the jurisdiction of a Federal or State agency, an agency created by Federal or State law, or an agency of a community participating in the NFIP that must assume ultimate responsibility for maintenance. This plan must document the formal procedure that ensures that the stability, height, and overall integrity of the levee and its associated structures and systems are maintained. At a minimum, maintenance plans shall specify the maintenance activities to be performed, the frequency of their performance, and the person by name or title responsible for their performance.

2.4 SUMMARY AND APPLICABILITY TO SBSP PROJECT

It is very likely that Federal funding will be sought for implementation of the restoration project, and the Army Corps and/or Fish and Wildlife Service may be the lead contracting agency for project construction. The project will also in all likelihood change existing flooding

characteristics in the area. This implies that levee construction and eventual certification will be based on requirements of both FEMA and the Army Corps.

Since flooding in the study area is influenced by both tides and river flow, site-specific Flood Insurance Studies will be required. Although flood protection benefits are quite likely after implementation of the restoration project, the effect of the restoration project, especially considering the long timeline for implementation, may be significant when interim flood management requirements are factored in.

3 EXISTING LEVEE ASSESSMENT

The existing salt pond levees were constructed for salt processing operations, and were not intended to provide a specific level of flood protection. As flood protection requirements were developed and refined to the current state described in Section 2 of this report, it also becomes clear that the levees do not meet *current* design requirements. However, the levees have nonetheless provided significant flood protection for adjacent urban areas. Coastal flooding has rarely overtopped the levees, and the level of flood protection appears to be consistent due to regular maintenance provided by the salt pond operators.

3.1 APPROACH

Data Collection

Digital ortho-photographs from USGS for the mid-90's time period were used as the base map for this analysis. The alignment of the Bay Trail was obtained from the Association of Bay Area Governments (ABAG) website. Several documents including feasibility studies and environmental documents prepared by the local flood control agencies were also reviewed.

Tide Gage information was obtained from data and reports published by the U.S. Army Corps of Engineers, the National Ocean Service, and prior reports for the study area.

Flood Insurance Rate Maps (FIRM) and Flood Insurance Studies (FIS) were obtained from FEMA to determine the areal extent and type of flooding in the project areas. Revisions to the FIRM due to Letters of Map Revision (LOMR) or Conditional Letters of Map Revision (CLOMR) as a result of recently constructed Flood Control Projects were not reviewed as part of this report; therefore current flood zone limits may vary slightly from limits shown on the FIRM.

Visual Reconnaissance Surveys

Hultgren-Tillis (HTE) and Moffatt & Nichol (M&N) conducted a feasibility-level visual reconnaissance survey of the existing levees in the Alviso and West Bay units in November and December 2003 to determine the general condition of the levees and adjacent topographic features. For each pond the existing urban levee was accessed and general conditions of the levees, such as crest width, slope geometry, levee condition, and presence of vegetation were recorded at various locations along the levees. Typical cross sections were recorded by pacing and by using a plunging hand level. Using centerline elevations from the ground survey provided by Tucker and Associates, the elevations were corrected to NGVD. The nature of the fill that makes up the existing levee was assessed by observing exposed surfaces. A sample form used for the field assessment is shown in Figure 3.1.1 and the forms themselves are provided in Appendix B.

A reference line was established for this study, for orientation and stationing during field work, and adjusted as needed to match field conditions. Generally, the reference line shown in this report follows established perimeter levees, some of which have been upgraded for pedestrian and vehicle traffic.

Topographic Survey

A topographic survey of existing levee elevations was conducted by Tucker & Associates in December 2003. The survey consisted of a series of spot elevations using kinematic and GPS survey methods taken along the levee crest centerline. Spot elevations were taken at 100-foot spacing (approximate) to provide a general profile of the levee and true positions (x, y, z coordinates) were recorded. Several benchmarks were also established and

monumented in the study area to serve as control for future survey efforts. The data are presented in plates in Appendix A, and average, typical elevations are shown in the figures attached to the main body of the report.

Geotechnical Analysis

Numerous soil investigation reports and boring logs were reviewed by HTE, including discussions with staff at Public Works Agencies for the adjoining Cities. The type of information obtained is described in Section 3.2.2.

3.2 EXISTING LEVEES – PHYSICAL CONDITIONS

Weak clays and silts (Bay Mud) are present at the surface of the project area. Since the site is located at the fringes of San Francisco Bay, changing the land use of the salt ponds to a tidal marsh will subject the landward-most salt pond levees to tidal and flood stages at the new margin of the Bay. In the past, these levees retained ponded water that had controlled water surface elevations. The existing levees were not well compacted when they were constructed. These soils are highly compressible and will continue to settle and deform for several years. Additional material will be needed to maintain design crest elevations as the levees settle. Though no shallow seepage was observed during the visual reconnaissance survey, re-compacting the existing levee fills will likely be required for any new levee improvements.

Loose to medium dense sands occur beneath portions of the site, which could liquefy during a strong earthquake. The breadth and freeboard of the final levee configurations may accommodate the expected deformations for most areas. However, ground improvement or modified levee alignments and cross-sections may be needed in some areas.

The SBSP restoration project will require raising the existing levees to reach specified elevations to provide tidal flood protection. Earth embankments used to raise and broaden the existing levees will be constructed over the Bay Mud. In many areas, the Bay Mud is too weak to allow the levees to be raised to their final heights without special considerations. These may include wide stability berms and/or wick drains. Placing the fill in vertical stages and allowing the underlying Bay Mud to consolidate and gain strength can be an effective method for building on weak soils, provided ample time (years) is allowed between filling stages.

3.2.1 Construction Method for Existing Levees

At the salt ponds, the levees were primarily constructed by excavating materials from within the ponds with the use of a dragline or clamshell and casting the excavated material to the side to form the levees. Periodically the levees were raised and widened using the same approach. Most of the salt pond levees consist predominately of cast-up bay mud. The initial heights of most salt pond levees did not need to be very high. Consequently, the underlying Bay Mud foundation materials were not usually overstressed.

Stability failures can occur in soft Bay Mud foundation materials if levee embankment fills are placed too high over a short period. The overloaded ground beneath the levee fill sinks and the adjacent mudflat heaves up. This type of failure is common when filling over soft ground too rapidly. It is commonly referred to as a "mudwave". Except for eroding levee faces, the existing salt pond levees are typically low to moderate in height and have fairly flat slopes. This configuration results in stable levees. The on-going maintenance filling adds or replaces eroded fill and creates moderately low loadings. These practices are sound for minimizing the risk of mudwaves.

In addition to diking of the ponds, several other areas were diked to create cells for refuse disposal. Solid waste landfills were created on the tidal flats and abut the salt ponds in these areas. The urban levees in the Alviso complex will abut the solid waste landfill dikes in Mountain View. Some dikes were created from imported soil, rock fragments, broken concrete and other predominately inorganic debris (rubble). The rubble-fill dikes typically have steeper slopes than the salt pond levees that are made from Bay Mud. One method for constructing rubble-fill dikes is to mound the fill high with steep side slopes and intentionally fail the ground, creating a mudwave. The rubble-fill displaces the Bay Mud creating a deep section of rubble fill. Rubble fill is pervious and is not well suited for creating levee sections with minimal seepage.

The landfill perimeter levee is likely constructed of clays, derived from imported fill and/or local Bay Mud. These levees should be of low permeability to control leachate seepage. A geometrically intuitive scheme for the urban levee would be to simply buttress the existing landfill slope and provide slope protection. However, the proximity of the new tidal waters to the landfill may be an issue for the landfill. Placement and design of the urban levee will need to be coordinated with the landfill owners and regulators. Leachate recovery wells with pneumatic pumps are located along the landfill perimeter. The geotechnical engineer will need to coordinate planned exploration locations with the landfill operator, checking that the pneumatic service and leachate extraction lines are identified as part of the utility clearances before drilling borings

3.2.2 Available Geotechnical Data

This feasibility study relies on existing geotechnical data. No new geotechnical data was developed as part of this study. Geotechnical characterization was accomplished by a combination of site visits and reviewing available existing data. Selected adjacent landowners and agencies were polled to locate existing geotechnical data near the salt pond levees that had been previously collected for various purposes. This data collection effort focused on data that could readily be obtained. The purpose was to provide data for a broad overview of the sub-surface conditions in the project area. Although additional data exists that was not obtained during this effort, sufficient data was identified to provide an overview appropriate for the feasibility study. This data collection should continue in subsequent preliminary design phases.

Data sources include:

- Town of Menlo Park
- City of Mountain View
- San Jose/Santa Clara Water Pollution Plant
- Santa Clara Water District
- City of Fremont
- California Geological Survey
- URS Corporation
- Hultgren-Tillis Engineers internal files

The locations of the borings and cone penetration tests which were collected are shown on Figures 3.2.2a through 3.2.2c. Copies of the boring and CPT logs are contained in Volume 2: Supplemental Data. To identify the borings/CPT's, each data point was assigned a unique name/number. The numbering system consists of three parts. The first part signifies the

name (or initials) of the company (or agency) that collected the data; the second part is the company's (agency's) project number, and the third part is the boring number assigned by the company (agency).

The geotechnical explorations primarily included drilled soil borings and pushed cone penetration tests (CPT) that were performed to obtain data for proposed structures or for environmental purposes. Limited data was found along the urban levee alignments or within the salt ponds. However, the data was sufficient to provide the broad overview that was sought for the feasibility study.

3.2.3 Subsurface Conditions

The young (Holocene) geologic unit upon which the existing levees and dikes were constructed is called San Francisco Bay Mud (Bay Mud). Based on a review of available geotechnical data, most of the levees are underlain by Bay Mud. Bay Mud consists of fine sediments that have settled out in the quiet waters of the San Francisco Bay estuary within the last 10,000 years. This material is predominately clay, has low strength and is highly compressible. Figure 3.2.3a shows the subsidence in the Santa Clara Valley between 1934 and 1967, which indicates that the pond levees may have settled as much as 4 to 5 feet due to groundwater extraction (SCVWD 2002). Figure 3.2.3b shows the amount of subsidence and groundwater levels in San Jose over a longer period (SCVWD 2002).

HTE estimated the elevation of the base of Bay Mud, based on selected exploration points from boring records. The data indicates that the Bay Mud extends to depths ranging from about -5 to -15 feet relative to NGVD in the majority of the Alviso and West Bay complexes. Deeper layers of Bay Mud were observed locally at existing creeks that create buried channels or fingers extending from the bay towards the land. The Bay Mud layer contains intermediate sand layers or lenses at various locations.

The Bay Mud typically overlies alluvial deposits, consisting primarily of medium stiff to stiff clays and loose to dense sands. Loose sands may also be present within the levee fills at some locations. In general, the clays and sands are of sufficient strength not to affect the existing static stability of the existing perimeter levees. The clays may be too weak in some areas to allow the new levees to be reliably constructed to final design heights in a single stage. Loose sands below the groundwater table may be at risk of liquefying during a large earthquake. These factors are discussed further herein.

3.2.4 Seismicity and Liquefaction

The project area lies between the San Andreas and Hayward faults. These two faults, the San Andreas and the Hayward, are classified as Type A faults by the California Department of Conservation Division of Mines and Geology (now part of the California Geological Survey). The nearest sections of the San Andreas fault to the various levees range from 10 kilometers (km) in Menlo Park to 26 km in Fremont and Newark. The Hayward fault to the east ranges from 6 kilometers to 19 kilometers from the levees. Four Type B faults lie near the levees on either side of the Santa Clara Valley. On the west side, the Monte Vista-Shannon Fault lies 8 to 22 km from the levees. To the east, the southeast Type B extension of the Hayward fault lies from 5 to 24 km from the levees. In addition, the Calaveras North and South fault segments are located from 11 to 29 km and 15 to 34 km east of the levees, respectively. Other faults with lower potential risk for strong seismic shaking may lie at closer distances than the above referenced faults. However, for seismic design the Type A and Type B faults described above may be used as the primary seismic source hazards for earthquake shaking.

The USGS has undertaken a seismic probability study in which it assesses the risk of occurrence of various levels of groundshaking from known fault sources in the vicinity. For a seismic risk of occurrence of 10 percent within 50 years, the peak acceleration for rock or very stiff soils at depth ranges from 0.44g to 0.64g below the salt pond levees.

Soil liquefaction is a phenomenon in which loose- to medium-dense saturated granular soil undergoes reduction of internal strength because of increased pore water pressure generated by shear strains within the soil mass. This behavior is most commonly induced by strong groundshaking associated with earthquakes. HTE judges that the loose and medium dense sands at the site will be susceptible to liquefaction. Though the levees may deform if sand layers within the foundation liquefy, broad, well-compacted levees with fairly flat slopes and ample freeboard will have minimal risk of overtopping or breaching. Assessing the liquefaction risk, estimating deformation and evaluating the resulting potential change in risk of overtopping/breaching will need to be addressed during subsequent design phases for the levees.

3.3 ALVISO COMPLEX

3.3.1 Existing Flooding

All of the Alviso Complex ponds are within the 100-year floodplain as defined by FEMA, with varying levels of potential flooding depending on the BFE and topography. The 100-year flood plain is shown on Figures 3.3.1a and 3.3.1b. Much of the surrounding area is flat and is thus also in the floodplain, with the exception of high ground associated with landfills in portions of Mountain View and San Jose. For the study area, stillwater elevations as described in various Flood Insurance Studies (FIS) performed by SCVWD and/or others for CLOMR applications, are as follows:

Presently Adopted 100-year Stillwater Elevations

(FEMA Flood Insurance Studies 1997, 1998, 1999)

Location	Elevation (ft, NGVD)
Palo Alto	7.7
Mountain View	8.0
Sunnyvale	8.0
Guadalupe Slough & Coyote Creek	8.1
SPRR & Alviso Slough	8.6
Milpitas	8.6

Available tidal benchmark data for tide stations near the Alviso Complex are presented in Table 3.3.1. However, many tide stations in the Alviso area were in operation for limited periods of time in the late 1970's; thus the data may not accurately reflect present conditions (M&N 2003).

Table 3.3.1 : Tidal Benchmark Data For Alviso Complex
(elevations in feet, MLLW)

Tidal Plane	941 4519 Mowry Slough	941 4521 Mud Slough Railroad Br.	941 4525 Palo Alto Yacht Harbor	941 4537 Palo Alto CM No 8	941 4548 Guadalupe Slough	941 4549 Upper Guadalupe Slough	941 4551 Gold Street Bridge	941 4561 Coyote Creek (Artesian SI)	941 4575 Coyote Creek (Alviso SI)	941 4589 Coyote Creek Tributary 2
Period Of Measurement	12/76 - 6/77	11/76 - 2/77	6/84 - 12/84	6/76 - 3/77	12/74 - 3/76	12/76 - 1/77	5/75 - 11/75	11/76 - 3/77	3/75 - 3/76 4/84 - 3/85	6/77 - 1/78
Duration of Measurements	6 mos	4 mos (highs only)	7 mos	10 mos (highs only)	16 mos (highs only)	2 mos	5 mos	5 mos	13 mos + 12 mos	4 mos (highs only)
100-YR	11.5	12	11.5	11.5	11.9	12.3	12.4	12.4	12.5	12.3
HOWL	10.2	-	--	-	10.3	11	11	10.7	10.8	-
MHHW	8.5	-	7.6	-	8.6	9.3	9.3	8.5	9	-
MHW	7.9	-	7	-	8	8.7	8.7	7.9	8.4	-
MTL	4.6	-	3.9	-	4.6	5	5	4.4	4.8	-
MLW	1.2	-	0.8	-	1.1	1.3	1.2	0.8	1.2	-
MLLW	0	-	0	-	0	0	0	0	0	-
LOWL	-	-	-	-	-0.7	-1.7	-1.2	-1	-1.8	-

Blank values indicate that specific tidal plane not computed

3.3.2 Physical Setting

The existing topography in the vicinity of the urban levee was determined by reviewing available documents, site visits, and field survey. The results are described below starting from the western limit at Pond A1, proceeding to the eastern limit at New Chicago Marsh (south of Pond A16). Ponds A22 and A23, which are physically isolated from the other ponds were also surveyed. Typical elevations based on the survey points, referenced to NGVD, are shown on figures. Pond elevations, for reference, are provided in Appendix C.

Pond A1

Figure 3.3.2a shows the pond, the surrounding area, the existing Bay Trail, and the urban levee reference line. Pond A1 is bounded to the north by the Bay, to the west by Charleston Slough and to the east by Mountain View Slough; further to the west is the large Palo Alto Floodbasin, which collects flow from Matadero, Barron, and Adobe Creeks prior to discharging into the Bay.

The far west portion of the pond's southern border abuts the Coast Casey Forebay, which serves as a flood control basin for Mountain View. This portion of the pond levee is relatively low, with elevations ranging from 8' to 9'. As part of the Bay Trail, the levee is paved with asphalt concrete and seems to be in good condition. The pond-side slope is relatively flat, vegetated, and appears to be in good condition.

Proceeding east, the trail rises to elevations of 15' to 17' as it borders the high ground of the Shoreline at Mountain View, which is built on a former landfill that is actively monitored. A wide, lower bench near the water line continues along the pond. Figure 3.3.2b shows a cross-section through this portion of the levee. The slope from the bench to the waterline is mild and vegetated with grasses.

Pond A2W

Figure 3.3.2c shows the pond and adjacent area, the existing Bay Trail, and the urban levee reference line. Pond A2W is bounded to the north by the Bay, to the west by Mountain View Slough, and to the east by Whisman Slough (Stevens Creek). To the south is the eastern half of the Shoreline at Mountain View. This southern border can be divided into three distinct parts depending upon the adjacent, landside features as described below.

The western portion of the pond's south border abuts the Mountain View Tidal Marsh, which is tidally connected to Mountain View Slough via several breaches through a low levee. The levee in this portion is surfaced with aggregate and is not part of the Bay Trail. The elevation of the levee crest gradually slopes up from west to east until it connects with the Bay Trail. A wide lower bench follows the levee crest near the waterline, with typical elevations ranging from 1' to 4'.

The main central portion of the levee is adjacent to high ground (former landfill) and is part of the paved Bay Trail. A wide lower bench continues, parallel to the trail, from the western portion. Figure 3.3.2d shows a cross-section through this portion of the levee. Note that the lower bench elevations range from 2' to 3', and that the levee crest (Bay Trail) is at an approximate elevation of 15'. The short slope from the lower bench to the waterline is highly eroded and nearly vertical.

The eastern portion borders the Stevens Creek Tidal Marsh. Passing through the marsh are two PG&E lines. The lower bench continues at elevations similar to the other portions, and also becomes an unpaved, unofficial part of the Bay Trail. The paved road continues south between the marsh and the landfill but is not a part of the Bay Trail.

Pond A2E/B2

Figure 3.3.2e shows the surrounding area and the urban levee reference line. Pond A2E is bounded to the north by Pond B1, to the west by Whisman Slough, and to the east by Pond B2. To the north of Pond B1 is the Bay. Pond B2 abuts a very short stretch of the urban levee, with the Bay to the north and Pond A3W to the east. Figure 3.3.2f shows a cross-section through this portion of the levee.

Generally, the area south of these ponds consists of the NASA/Ames Research Center in the west and Moffett Field in the east. The far western area is the Stevens Creek Shoreline Nature Study Area, operated by the Mid-Peninsula Regional Open Space District. The western portion of NASA's property contains two large ponded areas. One of them (east of the Nature Study Area) is a large stormwater retention pond. The other pond juts north into Pond A2E, to the north of Moffett Field, and is separated from the retention pond by a low, varying width berm that terminates just north of Moffett Field.

Pond A3W

Figure 3.3.2g shows the area, the existing Bay Trail, and the urban levee reference line. Pond A3W is bounded to the north by the Bay, to the west by Pond B2, and to the east by three different water bodies: 1) Guadalupe Slough; 2) Sunnyvale WPCP oxidation pond; and 3) a small, unnamed salt pond (not part of the purchased salt ponds). Figure 3.3.2h shows a cross-section through this portion of the levee.

South of the pond is Moffett Drain (or Northern Channel), a small ditch draining parts of Moffett Field. Along this ditch are posted numerous signs warning of the potential hazardous materials it may contain. South of the ditch is the Moffett Field Golf Course.

Oxidation Ponds

Figure 3.3.2i shows the area, the existing Bay Trail, and the urban levee reference line. The Oxidation Ponds, which are part of the Sunnyvale WPCP's treatment process, are bounded to the north by Guadalupe Slough, to the west by Pond A3W and the unnamed salt pond, and to the east by Moffett Channel. The unnamed salt pond borders the entire southern limit of the oxidation pond, and is presently not a part of the restoration project; it is owned by Cargill.

Pond A4

Figure 3.3.2j shows the area, the existing Bay Trail, and the urban levee reference line. Pond A4 is bounded to the northeast by Guadalupe Slough and to the northwest by Moffett Channel. South of the pond is the Sunnyvale WPCP, the SMaRT recycling center, and the Twin Creeks Sports Complex. Figure 3.3.2k shows a cross-section through this portion of the levee.

The pond is owned by SCVWD; plans are underway for restoration. Although not a part of the South Bay Salt Pond Restoration Project, the restoration of Pond A4 will have an effect, and will be affected by, the larger project.

The levee south of the pond ranges from approximately 6.5' to 10.5' NGVD. The levee also functions as the Bay Trail along the entire length of the pond, crossing a steel bridge over Sunnyvale East Channel.

Pond A8

Figure 3.3.2l shows the area, the existing Bay Trail, and the urban levee reference line. Pond A8 is bounded to the north and east by Alviso Slough, and to the west by Pond A7 and

A5. The far southwest and south is bordered by Guadalupe Slough. South of the slough is the eastern portion of the Sunnyvale Baylands Park, a bird preserve, and Harvey Marsh.

The elevation of the levee protecting the park from high water in the slough ranges from 10' to 11' NGVD. The levee also is part of the Bay Trail along the park, turning south to follow Calabazas Creek. Several interior levees cross east-west along the southern portion of the pond, some of which support a least tern nesting area.

New Chicago Marsh, Pond A12, Pond A13, Pond A16

Figures 3.3.2m and 3.3.2n shows the area, the existing Bay Trail, and the urban levee reference line. New Chicago Marsh is bounded to the north by Pond A16, to the east by Artesian Slough, to the northwest by Pond A13, to the west by Pond A12, and to the south by the town of Alviso. Along the western edge of the marsh is the SPRR railroad line. The southwest corner of the marsh abuts the Alviso Marina. Figure 3.3.2o shows cross-sections fronting the marsh through this portion of the levee.

The marsh has subsided significantly over time, and would be completely inundated if subjected to tidal water. The levee protecting the town of Alviso varies in elevation from approximately 0' to almost 10.0' NGVD, indicating that flood protection is largely provided by the salt pond levees and the Bay Trail levee.

Pond A22

Figure 3.3.2p shows the area and the urban levee reference line. The pond is bounded to the northeast by Cushing Parkway and to the northwest by Refuge lands, to the west by the SPRR railroad, to the east by Mud Slough and to the south by Pond A23. Figure 3.3.2q shows a cross-section through the levee between the pond and Refuge lands. Since urban development is to the north, only this portion of the pond levee was surveyed.

The pond was dry during the site visit, and borrow ditches were observed 15 to 20 feet from the pondside toe of levee.

Pond A23

Since no urban communities abut against the pond levees, this pond was not surveyed. It should be noted however, that the SPRR railroad runs along the west side of the pond and may prove to be a constraint to full tidal restoration.

3.4 WEST BAY COMPLEX

3.4.1 Existing Flooding

The current level of flooding can be reasonably ascertained by examination of the FIRMs in the project area. Generally speaking, the salt ponds are currently in the SFHA throughout the project. The 100-year floodplain is shown on Figure 3.4.1a. Areas immediately landward of the salt ponds are typically in SFHA or in Zone X.

Available tidal benchmark data for tide stations near the West Bay Complex are presented in Table 3.4.1.

Table 3.4.1 : Tidal Benchmark Data For West Bay Complex
(elevations in feet, MLLW)

Tidal Plane	941 4501 Redwood Creek	941 4507 Westpoint Slough	941 4509 Dumbarton Bridge	941 4525 Palo Alto Yacht Harbor	941 4537 Palo Alto CM No. 8
100-YR	11.00	11.2	11.6	11.5	11.5
HOWL	9.63	--	10.2	--	--
MHHW	7.96	8.0	8.5	7.6	--
MHW	7.35	7.4	7.9	7.0	--
MTL	4.27	4.3	4.5	3.9	--
NGVD	3.91	--	4.1	--	--
MLW	1.19	1.2	1.2	0.8	--
MLLW	0.00	0.0	0.0	0.0	--
LOWL	-2.10	--	-2.2	-2.1	--

3.4.2 Physical Setting

The results of the field survey are shown in Figures 3.4.2a to 3.4.2e. Note that the aerial photographs are approximately 12 years old and do not show the Sun Microsystems campus between Pond 3 and Highway 84.

Pond S5

Figure 3.4.2a shows the pond, the surrounding area, and the reference line. The pond is bounded by a drainage ditch (Bayfront Canal) and Highway 84 to the south, other ponds to the north and east, and County property to the west where a pump structure exists. Figure 3.4.2b shows a cross-section through this portion of the levee. The pond was dry during the site visit and crystallized salt was observed on the surface.

Pond 3

Figure 3.4.2c shows the pond, the surrounding area, and the reference line. The pond is bounded by Highway 84 to the south, Ravenswood Slough to the northeast, other ponds (ponds 4 and S5) to the northwest and west. Figure 3.4.2d shows a cross-section through the portion of levee fronting Highway 84. The pond was dry in many areas during the site visit, and a significant amount of crystallization of salt was observed on the surface.

Pond SF2

Figure 3.4.2e shows the pond, the surrounding area, and the reference line. Urban development adjacent to the pond include Highway 84 to the north and west and the SPRR railroad to the south.

3.5 BAUMBERG COMPLEX

3.5.1 Existing Flooding

The primary watershed in the Baumberg complex is the Alameda Creek watershed, with a total area of about 695 square miles. The watershed discharges into San Francisco Bay via the Alameda Creek Flood Control Channel.

Previous reports (URS 2002) state that the Alameda Creek Flood Control channel was designed to protect surrounding lands from the standard project flood, which is the flood with a return period of approximately 500 years. Due to siltation, the channel's capacity has lessened, but still provides significant protection from the 100-year event. During this event, the southern levees are above the water surface but the northern levees are overtopped in the downstream reaches (below Ardenwood Blvd.), resulting in moderate flooding of undeveloped areas. Figure 3.5.1 shows the 100-year floodplain, as simulated using hydraulic analysis described in the report.

Available tidal benchmark data for tide stations near the Baumberg Complex are presented in Table 3.5.1.

Table 3.5.1 : Tidal Benchmark Data For Baumberg Complex
(elevations in feet, MLLW)

Tidal Plane	941 4458 San Mateo Bridge (West End)	941 4637 San Mateo Bridge (East End)	941 4621 Coyote Hills Slough	941 4632 Alameda Creek
Period Of Measurement	1/81 – 1/88	1/77 – 3/77	12/76 – 3/77	12/76 – 3/77
Duration of Measurements	7 yrs	3 mos	4 mos	3 mos
100-year Estimated Tide (USACE)	10.7	10.7	--	9.1
Highest Observed Water Level ¹	10.7	9.2	8.3	7.6
Mean Higher High Water (MHHW)	7.7	7.7	6.7	6.1
Mean High Water (MHW)	7.1	7.1	6.1	5.5
Mean Tide Level (MTL)	4.1	4.1	3.3	2.9
Mean Sea Level	4.1	-	-	-
National Geodetic Vertical Datum, 1929 (NGVD) ²	3.6	3.7	-	-
Mean Low Water (MLW)	1.2	1.2	0.5	0.3
Mean Lower Low Water (MLLW)	0.0	0.0	0.0	0.0
Lowest Observed Water Level	-2.9	-1.8	-0.3	-0.3

Blank values indicate that specific tidal plane not computed

¹ Extreme levels during the period of measurement

² Elevation of NGVD is approximate, based on data from NOS and USACE (1984)

3.5.2 Physical Setting

The existing topography in the area of the proposed urban levee is relatively flat, with three significant waterways passing through – the Alameda Creek Flood Control Channel (Coyote Hills Slough), the old Alameda Creek, and Mount Eden Creek. Figure 3.5.2a shows a layout of the study area investigated by URS for the ACFCWCD, including a station line which can be used to determine cross section locations. Figure 3.5.2b shows cross sections through the Flood Control Channel levees. The proposed urban levee essentially follows the reference line previously determined by the Alameda Creek Levee Reconfiguration Project (ACLRP) with minor alterations.

Since a detailed flood control investigation is already being conducted by the ACFCWCD, including field and LiDAR surveys, the visual reconnaissance did not extend into this area. The URS report also includes a detailed photo log of conditions in the area.

4 PROPOSED LEVEE IMPROVEMENTS

4.1 DESIGN ASSUMPTIONS

As previously stated, the reference line of the proposed urban levee was developed by reviewing previous alignments and adjusting them as needed to fit field conditions; thus the reference line follows existing levees and/or trails along the salt pond. It should also be noted that the urban levee ends at intersections with waterways and does not continue upstream along riverbanks; as such, the urban levee functions as a coastal levee as opposed to a riverine levee.

The geometry (height, width, slope) of the proposed urban levee depends on WSEL, extent of wind/wave action, geotechnical stability, construction method, and need for public access along the crest among others. For purposes of this report, several assumptions were made:

- Exposure to wind and waves will depend on the restoration alternative selected for each pond, which is not known at this stage. Therefore two levee sections are assumed for this analysis, one with fetch breaks (limiting wind waves to < 1 foot) and one without fetch breaks. The crest elevations were estimated to be +12 feet (with fetch break) and +14.5 (no fetch break). These elevations are consistent with estimates developed as part of the SFO Airport hydrodynamic studies (ADEC 2002) for tidal marsh restoration at the salt ponds. The SFO studies provide details on the methodology used to estimate wave run-up and wave overtopping.
- The assumed construction method is excavating material from the pond interior using draglines or similar equipment, and placing on the existing levees at the required slopes. Since the material will have a high moisture content, the construction is expected to be slow, and will keep pace with material conditioning and compaction. The large quantity of required material makes importing borrow fill cost-prohibitive, but may be necessary in areas where adequate volume and quality of borrow material is not available.
- A levee crest of 20-feet and slopes of 3H:1V and 8H:1V were assumed in the analysis. The wide crest will allow placement of additional material if excessive consolidation and/or settlement occurs. The relatively flat side slopes will provide a wide footprint for stability. The cases analyzed were as described in the following.

Crest Elevation	Side slope
(ft, NGVD)	(Horizontal : Vertical)
+12	3 : 1
+12	8 : 1
+14.5	8 : 1
+15.5	3 : 1

The Baumberg complex, specifically the Alameda Creek Flood Control Channel, has been studied in more detail by ACFCWCD. A recent report² provides a thorough analysis of flood protection requirements for this major waterway which will be utilized in this section.

² URS, Alameda Creek Levee Reconfiguration Project, August 2002.

4.2 ANTICIPATED POST-PROJECT HYDRODYNAMICS

Changes in the hydraulic parameters of significance – water levels, velocity, and circulation – will result in changes in conveyance capacity and a corresponding change in the level of existing flood protection.

Changes in tidal water levels in any of the creeks will be highly dependent on changes in tidal prism in the creek itself. A substantial increase in tidal prism in a fully tidal channel will usually result in a short-term (on the order of months) lowering of high water level, a change in the time of high water level, and increase in channel velocity. The lowering of high water, or “tidal muting”, is explained by the fact that the tidal period (time between successive high or low tides) does not change, and the increase in inundated area and water volume due to pond breaching is compensated by a reduction in tidal range over the entire inundated area.

The data reviewed indicates that tidal flooding by itself is not a significant issue. However, flooding concerns arise at times of high stormwater flows combined with extreme high tides. If the elevation of high tide near the mouths of the sloughs/creeks do not change, then there will be no apparent change in the level of flood protection that the levees presently offer. However, if there are changes in the level of high tide upstream of the mouth, then the level of flood protection will change.

It is quite likely that breaches through the existing Bayfront pond levees may not result in any increase in high tide elevation upstream of the creek mouth. Instead, there may actually be benefits to flood conveyance since the restored ponds would allow routing of storm flows over existing slough levees (by constructing sills or overflow weirs).

Unfortunately, not all ponds have Bayfront levees, and restoration of some of the interior ponds may involve breaching through the slough levees. Breaches through the existing slough levees may result in changes in levels and time of high water, depending on the size of the existing slough. Sloughs with large cross sectional areas may not result in differences in high tide elevation between the mouth of the sloughs and upstream near the breach. However, some of the smaller sloughs where the high tide is muted due to shallow depths may see an increase in high tide elevation, resulting in flooding concerns farther upstream (due to higher backwater).

4.3 GEOTECHNICAL ASSESSMENT

4.3.1 Assumed Soil Properties for Settlement and Slope Stability Analyses

For 20 representative sections along the levees, preliminary estimates of settlement and the immediately-after-construction factor of safety for slope stability were made. For both analyses, HTE used “typical” Bay Mud properties.

To estimate the magnitude of settlement, a compression ratio (C_{EC}) of 0.30 was used. For the purpose of our analyses, average unit weights of 94 pounds per cubic foot for the Bay Mud and 120 pounds per cubic foot for new and existing fill were used. It was assumed that the shallow Bay Mud is slightly over-consolidated due to desiccation and/or previously lowered groundwater levels and that the Bay Mud is normally consolidated below a depth of about ___ feet.

To assess the strength of the Bay Mud foundation materials, HTE reviewed available data. From this review, coupled with past experience on Bay Mud sites, HTE concluded that the undrained shear strength of the Bay Mud beneath the ponds could be characterized as between 200 pounds per square feet (psf) and 400 psf. HTE judges this range to represent the condition of normally consolidated clay and that of slightly over consolidated clay. Both

conditions are reasonably to be expected along the length of the salt pond perimeter levee. HTE chose to assess the feasibility-level slope stability of future levee embankments using both of these average shear strength values.

4.3.2 Assumed Levee Profiles For Settlement and Slope Stability Analyses

Four levee design profiles were applied to 20 typical sections for estimating settlement and the immediately-after-construction factor of safety. The factors that differentiated the design profiles were the inclination of the waterside slope and the design crest elevation (DCE). The crest width of at least 20 feet was assumed. The following crest elevations and waterside slopes were used for the four design profiles that were analyzed:

- Design Crest Elevation = +12 ft with a 3:1 waterside slope
- Design Crest Elevation = +12 ft with an 8:1 waterside slope
- Design Crest Elevation = +14.5 ft with an 8:1 waterside slope
- Design Crest Elevation = +15.5 ft with a 3:1 waterside slope

The first two design profiles were used for the condition of having an intermediate fetch break that limits wave run-up, and the last two profiles assumed that there was an unrestricted fetch into the Bay. The flatter slope was used for reduced wave run-up.

4.3.3 Settlement and Slope Stability Analysis

By repeated trial, HTE placed varying thicknesses of embankment fill and checked the resulting settlement until such thickness was developed that would maintain the design crest elevations. Settlement estimates for various crest elevations and thicknesses of Bay Mud deposits are presented on Figures 4.3.3a through 4.3.3m for the various cross-sections.

For soft clay sites such as Bay Mud, the controlling stability condition is that which occurs during-construction or immediately-after-construction of the levee embankment. If the levee fill were to be placed over a long period of time (years), the underlying clay would have time to drain and gain strength. For the long-term (drained) condition, slope stability is seldom a concern. For final slope configurations of 3:1 or flatter, HTE concludes that long-term stability for the urban levees will not be a concern. The critical case occurs when the load is first placed. At that time, no drainage has occurred and, as a direct result, no strength gain has occurred. Most of the new load is taken up by increases in pore pressure within the soil as the new loads are placed. Strength gain occurs only as the excess pore water pressure drains, allowing the soil particles to press together increasing the strength. For this reason, the controlling condition for clay sites occurs either as the loads are placed or immediately after they have been placed.

For this feasibility study, HTE assessed the factor of safety of the levee embankments assuming that they were built instantaneously and that they were initially constructed to between 1 to 1.5 feet above their design crest elevations. This additional fill thickness allows for a combination of overbuild to account for settlement as well as a simplified way to model for a somewhat greater mass of fill that will occur due to immediate compression and shear deformation in the foundation materials.

The purpose of the stability analysis presented herein is to provide an initial screening assessment to demonstrate the impact that existing levee and pond elevations have on the typical levee heights and slopes. The primary focus was the stability assessment on the bay side of the levee where the greatest quantities of fill will be placed. In some areas, the existing levees are quite low and new fill thicknesses will create substantial loading on the

upslope side of the levee. The stability in the upslope direction was not addressed during the stability analyses for this feasibility study. Further stability assessments will be needed during levee siting and development of the levee configurations. The geotechnical engineers will need to assess the factors of safety during various stages of filling for areas where the immediately-after-construction factor of safety is less than the design value selected by the owners (commonly a factor of safety of 1.3).

As part of the stability screening procedure, stability charts were prepared for use in assessing the stability of the levees for various heights of fill embankment and various thicknesses of Bay Mud deposits. These charts were developed both for 3:1 and 8:1 slopes. Charts were prepared for two Bay Mud shear strengths, 200 psf and 400 psf. These stability analysis charts are presented on Figures 4.3.3n and 4.3.3o. In preparing these charts, an assumed average unit weight of 115 pcf applied to both the new fill as well as the underlying Bay Mud. These charts were derived using the stability design chart titled "Stability Analysis for Slopes and Cohesive Soils Undrained Conditions" published in the Naval Facilities Design Manual DM7, page 7.1-319. Using these stability analysis charts, the short term / immediately-after-construction stability for the new levee embankments was estimated. For those embankments whose design crest elevations were at Elevation 14.5 and 15.5 feet, it was assumed that the embankments would be constructed 1.5 feet higher than the design crest elevation to allow for the initial aspects of settlement. Where the embankment at design crest elevation is 12 feet, it was assumed that one additional foot of fill would be placed to elevation 13. The resulting computed factors of safety for these thicknesses of embankment fill are presented for various thicknesses of Bay Mud on Figures 4.3.3a through 4.3.3m

The stability charts were prepared for "thicknesses" of Bay Mud. Previous sections of this report have described the collection of existing data and reported that the elevation of the base of the mud was typically between Elevation -5 and -15 feet NGVD. The elevation within the ponds is typically between - 3 to + 3 feet. Clearly, the thickness of the mud is a function of the elevation of the bottom of the ponds as well as the elevation of the base of the mud. For this feasibility level study, the data available on the base of the mud is not precise beyond the general descriptions that have been used.

4.3.4 Levee Construction Issues

The two major geotechnical factors affecting the construction of new levees are the strength of the Bay Mud and its compressibility. The low strength will limit the height at which the levees can be initially constructed in some areas. For much of the salt marsh perimeter, the levees may need to be constructed in two stages. The time between filling stages will allow the underlying clays to consolidate and gain strength. The levees will continue to settle after they are constructed to their designed crest elevations. The levee crests will need to be designed with sufficient width to accommodate placing additional fill to maintain the levee crest design elevations.

In addition to settlement of the Bay Mud, there is an on-going longer term consolidation occurring in the deeper sediments in the Santa Clara Valley basin. This deep consolidation is the result of groundwater withdrawal. Though the extraction of groundwater is now well managed and the rates of settlement have decreased substantially, some on-going regional settlement is still occurring. Extrapolating the rate of regional consolidation over the last twenty to thirty years suggests that an additional foot of settlement can be expected over a period of 30 years along portions of the urban levee. In addition, sea level rise, and sedimentation within the restored ponds adjacent to the levee will occur. These factors would be addressed by raising the levee periodically.

4.3.5 Geotechnical Discussion and Conclusions

The most important factor affecting stability of the embankments in this locale is the strength of the foundation soils. The strength of the foundation soils limits the height to which the levee can be built and how fast it can be built. The primary guideline for raising an embankment on Bay Mud is to limit the height of each stage of construction so that an adequate factor of safety against stability failure for that stage of construction is maintained. For thick fills it may be necessary to have several stages of construction, allowing the mud to consolidate and gain strength between the stages. For the South Bay levees, many of the levees will be of sufficient height that they will have to be constructed in two stages, with the second stage bringing the levee to its design crest elevation. One of the methods that can be used to improve stability is to place wide stability berms at the levee toe. These berms offset the tendency of the toe to heave, creating a buttress or weight at the levee toe, increasing its overall stability. Using flat slopes can also improve the stability of slopes. Wick drains may be used to accelerate consolidation. However, the increased risk of underseepage that a drainage blanket would cause must be assessed.

Levees will need to be overbuilt to allow for settlement that will occur after the levees have been constructed. The suggested plan would be to construct them 1 to 1.5 feet above the design crest elevations and to make the crest levees wide enough so that as the levees settle, additional fill can be placed to achieve the final design crest elevation while still having a sufficiently wide final levee crest.

Levees need to control seepage. Seepage can be subdivided into two primary seepage zones: that which occurs through the levee embankment and that which flows through aquifers or other formations beneath the levees. During the site visits, indications of seepage through the levees was not observed. The new urban levees will be much taller and broader and will be well compacted. The risk of adverse seepage through the new levee embankments will be small.

For the deeper seepage, there may be changes with time in the groundwater profile. The project will change the average head of water in the ponds compared to the head when they stored water for salt manufacturing. A closer look will have to be taken to see if the project will be raising or lowering the heads because the ponds elevations vary. With the low permeability of the Bay Mud which underlies the ponds, the changes in groundwater levels below the Bay Mud will likely be small. Further assessment may conclude the affect on groundwater levels may be insignificant relative to other stressors on the hydrogeology.

4.4 DESIGN AND COST ESTIMATE

Based on the design assumptions described in the previous section, a planning-level design and corresponding cost estimate was developed. The estimate is presented as a cost for each pond, and includes construction, engineering, surveying, geotechnical studies, environmental studies, construction administration, and contingencies. For simplicity, a single cross-sectional design was developed for each pond to represent the typical features of the pond.

4.4.1 Alviso Complex

The Alviso complex passes through varied topographical features, and thus has greater variation in cross-section than the other complexes. The design cross-section for each pond in the Alviso complex is shown in Figure 4.4.1. Quantities and costs associated with each pond levee are shown on Tables 4.4.1a and 4.4.1b.

4.4.2 West Bay Complex

The typical design cross-section for pond S5 and pond 3 in the West Bay complex is shown in Figure 4.4.2, and Tables 4.4.2a and 4.4.2b show the quantities and costs anticipated for each pond in the West Bay complex.

4.4.3 Baumberg Complex

The Alameda Creek Levee Reconfiguration Project (URS, 2000) provided several options to increase the level of flood protection to its original, design level. The Alameda Creek Flood Control channel (or Coyote Hills Slough) was designed to provide protection from the Standard Project Flood (SPF), which roughly corresponded to a 500-year event. Currently, the channel does not provide this level of protection, and of various options proposed, option D best resembles the Salt Pond Restoration Project features. This option would include multiple levee breaches along the channel, allowing flow into ponds between the channel and Old Alameda Creek to the north. The levee breaches assumed in the URS report would also expose these ponds to tidal influence, with a corresponding increased potential for coastal flooding to urban areas.

It is important to note that the levees in the ACLRP are designed to meet criteria that differs from the Alviso and West Bay complexes. First, the levees must contain fluvial flood waters, as opposed to coastal flood waters. The water surface profile of the channel in the easternmost region of the complex is much higher than at the mouth of the channel, resulting in levee crest elevations that are several feet higher than would be required for coastal flooding only. Secondly, the SPF is a more severe flood event than the 100-year event used in the other complexes.

The continuous urban levee reference line in the Baumberg complex was assumed to follow the alignment proposed in the ACLRP. Additionally, the ACLRP provided an estimated quantity of material needed to construct the urban levee. Thus, in lieu of performing new studies and analyses, and given the advanced nature of the previous investigation, the information provided in the ACLRP will be utilized in this section.

The summary of quantities and cost estimate for the Baumberg complex is shown in Table 4.4.3

4.5 ITEMS FOR FURTHER STUDY

Much of the information presented in this report is based on assumptions which warrant further investigation. Some of these issues are:

- Alignment – Along several ponds there are possible alternative alignments of the urban levee, some of which should be seriously considered. Pond A2E currently shows a levee protecting a large private pond which may not need protection. Pond A3W shows a levee protecting a small ditch (Moffett Drain) with a levee to the landside of the ditch; this alignment may be revised landward by filling in the ditch, if desired. New Chicago Marsh shows a levee along the Marsh border with the town of Alviso; this may result in flooding of the Marsh and a loss of significant marsh habitat. A levee following either the SPRR tracks, or the boundaries of Ponds A12-A13-A16 may be an alternate alignment to protect the marsh from inundation. These are a sampling of the possibilities for further study.
- Coordination with related projects such as Pond A4, Pond A16, Lower Guadalupe River Flood Control Project. These projects will have some effect on the hydraulics of

the project vicinity. Whether these related projects improve or degrade the overall system is a matter for additional study.

- Flood insurance considerations – the benefit of providing levees which meet FEMA certification requirements is to remove communities from areas with flood insurance requirements. However, there is no requirement on the part of the levee owner to meet FEMA requirements, rather only to provide the same protection currently provided.
- Loose and medium dense sands are present below the water table at the site. These soils are subject to liquefaction during a large magnitude earthquake in the vicinity. HTE's preliminary judgement is that broad, well-compacted levee embankments with properly maintained freeboard and with moderately flat side slopes can tolerate considerable liquefaction induced deformation without significant risk of overtopping or breaching. A more thorough evaluation of seismic risk and deformation will need to be addressed during subsequent design phases.

Table 4.4.1a - Estimated Quantities for Levee Construction

Alviso Complex

Pond	Begin Station	End Station	Length	Levee Crest Elevation (ft, NGVD)	Slope	Total Volume (CY)
A1	0	600	600	12.0	8:1	19,000
				14.5	3:1	13,000
				14.5	8:1	29,000
A1	600	1300	700	12.0	8:1	18,000
				14.5	3:1	9,000
				14.5	8:1	32,000
A1	1300	4300	3000	12.0	8:1	127,000
				14.5	3:1	91,000
				14.5	8:1	185,000
A2W	0	3750	3750	12.0	8:1	190,000
				14.5	3:1	139,000
				14.5	8:1	264,000
A2W	3750	4800	1050	12.0	8:1	79,000
				14.5	3:1	50,000
				14.5	8:1	105,000
A2E	0	1700	1700	12.0	8:1	67,000
				14.5	3:1	50,000
				14.5	8:1	99,000
A2E	1700	4100	2400	12.0	8:1	152,000
				14.5	3:1	106,000
				14.5	8:1	205,000
A2E	4100	6800	2700	12.0	8:1	164,000
				14.5	3:1	117,000
				14.5	8:1	222,000
A3W	6800	9400	2600	12.0	8:1	146,000
				14.5	3:1	96,000
				14.5	8:1	203,000
A3W	9400	11400	2000	12.0	8:1	117,000
				14.5	3:1	84,000
				14.5	8:1	159,000

Table 4.4.1b - Concept Level Costs for Levee Construction

Alviso Complex

	LENGTH (ft)	Levee Crest Elevation 12'				Levee Crest Elevation 14.5'				Levee Crest Elevation 14.5'			
		8:1 Slope				3:1 Slope				8:1 Slope			
		QTY	UNIT	UNIT COST	COST	QTY	UNIT	UNIT COST	COST	QTY	UNIT	UNIT COST	COST
Alviso Complex													
Pond A1	4300												
Mob / Demob		1	LS	\$120,000	\$120,000	1	LS	\$130,000	\$130,000	1	LS	\$180,000	\$180,000
Earthwork		164,000	CY	\$10	\$1,640,000	113,000	CY	\$15	\$1,695,000	246,000	CY	\$10	\$2,460,000
Clear & Grub		5.0	AC	\$5,000	\$25,000	5.0	AC	\$5,000	\$25,000	5.0	AC	\$5,000	\$25,000
Engineering (15%)		1	LS	\$250,000	\$250,000	1	LS	\$258,000	\$258,000	1	LS	\$373,000	\$373,000
Contract Administration (8%)		1	LS	\$133,000	\$133,000	1	LS	\$138,000	\$138,000	1	LS	\$199,000	\$199,000
Environmental / Permits (5%)		1	LS	\$83,000	\$83,000	1	LS	\$86,000	\$86,000	1	LS	\$124,000	\$124,000
Contingency (20%)		1	LS	\$333,000	\$333,000	1	LS	\$344,000	\$344,000	1	LS	\$497,000	\$497,000
Total Pond A1					\$2,584,000				\$2,676,000				\$3,858,000
Pond A2W	4800												
Mob / Demob		1	LS	\$200,000	\$200,000	1	LS	\$210,000	\$210,000	1	LS	\$280,000	\$280,000
Earthwork		268,000	CY	\$10	\$2,680,000	188,000	CY	\$15	\$2,820,000	369,000	CY	\$10	\$3,690,000
Clear & Grub		6.0	AC	\$5,000	\$30,000	6.0	AC	\$5,000	\$30,000	6.0	AC	\$5,000	\$30,000
Engineering (15%)		1	LS	\$407,000	\$407,000	1	LS	\$428,000	\$428,000	1	LS	\$558,000	\$558,000
Contract Administration (8%)		1	LS	\$217,000	\$217,000	1	LS	\$228,000	\$228,000	1	LS	\$298,000	\$298,000
Environmental / Permits (5%)		1	LS	\$136,000	\$136,000	1	LS	\$143,000	\$143,000	1	LS	\$186,000	\$186,000
Contingency (20%)		1	LS	\$542,000	\$542,000	1	LS	\$570,000	\$570,000	1	LS	\$744,000	\$744,000
Total Pond A2W					\$4,212,000				\$4,429,000				\$5,786,000
Pond A2E	6800												
Mob / Demob		1	LS	\$290,000	\$290,000	1	LS	\$300,000	\$300,000	1	LS	\$390,000	\$390,000
Earthwork		384,000	CY	\$10	\$3,840,000	272,000	CY	\$15	\$4,080,000	525,000	CY	\$10	\$5,250,000
Clear & Grub		8.0	AC	\$5,000	\$40,000	8.0	AC	\$5,000	\$40,000	8.0	AC	\$5,000	\$40,000
Engineering (15%)		1	LS	\$582,000	\$582,000	1	LS	\$618,000	\$618,000	1	LS	\$794,000	\$794,000
Contract Administration (8%)		1	LS	\$310,000	\$310,000	1	LS	\$330,000	\$330,000	1	LS	\$423,000	\$423,000
Environmental / Permits (5%)		1	LS	\$194,000	\$194,000	1	LS	\$206,000	\$206,000	1	LS	\$265,000	\$265,000
Contingency (20%)		1	LS	\$776,000	\$776,000	1	LS	\$824,000	\$824,000	1	LS	\$1,058,000	\$1,058,000
Total Pond A2E					\$6,032,000				\$6,398,000				\$8,220,000
Pond A3W	11400												
Mob / Demob		1	LS	\$200,000	\$200,000	1	LS	\$200,000	\$200,000	1	LS	\$270,000	\$270,000
Earthwork		263,000	CY	\$10	\$2,630,000	180,000	CY	\$15	\$2,700,000	361,000	CY	\$10	\$3,610,000
Clear & Grub		13.0	AC	\$5,000	\$65,000	13.0	AC	\$5,000	\$65,000	13.0	AC	\$5,000	\$65,000
Engineering (15%)		1	LS	\$404,000	\$404,000	1	LS	\$415,000	\$415,000	1	LS	\$551,000	\$551,000
Contract Administration (8%)		1	LS	\$216,000	\$216,000	1	LS	\$221,000	\$221,000	1	LS	\$294,000	\$294,000
Environmental / Permits (5%)		1	LS	\$135,000	\$135,000	1	LS	\$138,000	\$138,000	1	LS	\$184,000	\$184,000
Contingency (20%)		1	LS	\$539,000	\$539,000	1	LS	\$553,000	\$553,000	1	LS	\$735,000	\$735,000
Total Pond A3W					\$4,189,000				\$4,292,000				\$5,709,000

Table 4.4.2a - Estimated Quantities for Levee Construction

West Bay Complex

Pond	Begin Station	End Station	Length	Levee Crest Elevation (ft, NGVD)	Slope	Total Volume (CY)
WB-S5	0	3000	3000	12.0	8:1	55,000
				14.5	3:1	54,000
				14.5	8:1	92,000
WB-3	3000	7000	4000	12.0	8:1	57,000
				14.5	3:1	52,000
				14.5	8:1	111,000
WB-3	7000	11800	4800	12.0	8:1	81,000
				14.5	3:1	70,000
				14.5	8:1	148,000

West Bay Complex

	LENGTH (ft)	Levee Crest Elevation 12'				Levee Crest Elevation 14.5'				Levee Crest Elevation 14.5'			
		8:1 Slope				3:1 Slope				8:1 Slope			
		QTY	UNIT	UNIT COST	COST	QTY	UNIT	UNIT COST	COST	QTY	UNIT	UNIT COST	COST
West Bay Complex													
Pond S5	3000												
Mob / Demob		1	LS	\$40,000	\$40,000	1	LS	\$60,000	\$60,000	1	LS	\$70,000	\$70,000
Earthwork		55,000	CY	\$10	\$550,000	54,000	CY	\$15	\$810,000	92,000	CY	\$10	\$920,000
Clear & Grub		3.0	AC	\$5,000	\$15,000	3.0	AC	\$5,000	\$15,000	3.0	AC	\$5,000	\$15,000
Engineering (15%)		1	LS	\$85,000	\$85,000	1	LS	\$124,000	\$124,000	1	LS	\$140,000	\$140,000
Contract Administration (8%)		1	LS	\$45,000	\$45,000	1	LS	\$66,000	\$66,000	1	LS	\$75,000	\$75,000
Environmental / Permits (5%)		1	LS	\$28,000	\$28,000	1	LS	\$41,000	\$41,000	1	LS	\$47,000	\$47,000
Contingency (20%)		1	LS	\$113,000	\$113,000	1	LS	\$165,000	\$165,000	1	LS	\$187,000	\$187,000
Total Pond S5					\$876,000				\$1,281,000				\$1,454,000
Pond 3	11800												
Mob / Demob		1	LS	\$110,000	\$110,000	1	LS	\$140,000	\$140,000	1	LS	\$200,000	\$200,000
Earthwork		138,000	CY	\$10	\$1,380,000	121,000	CY	\$15	\$1,815,000	259,000	CY	\$10	\$2,590,000
Clear & Grub		14.0	AC	\$5,000	\$70,000	14.0	AC	\$5,000	\$70,000	14.0	AC	\$5,000	\$70,000
Engineering (15%)		1	LS	\$218,000	\$218,000	1	LS	\$283,000	\$283,000	1	LS	\$399,000	\$399,000
Contract Administration (8%)		1	LS	\$116,000	\$116,000	1	LS	\$151,000	\$151,000	1	LS	\$213,000	\$213,000
Environmental / Permits (5%)		1	LS	\$73,000	\$73,000	1	LS	\$94,000	\$94,000	1	LS	\$133,000	\$133,000
Contingency (20%)		1	LS	\$290,000	\$290,000	1	LS	\$377,000	\$377,000	1	LS	\$532,000	\$532,000
Total Pond 3					\$2,257,000				\$2,930,000				\$4,137,000

Table 4.4.3a - Estimated Quantities for Levee Construction
Baumberg Complex

Begin Station	End Station	Length	TOTAL OVERBUILT AREA, SF	Slope	Total Volume (CY)
0	38140	38140	varies	2:1	194,000

Table 4.4.3b - Concept Level Costs for Levee Construction
Baumberg Complex

	LENGTH (ft)	QTY	UNIT	UNIT COST	COST
<u>All</u>	38140				
Mob / Demob		1	LS	\$190,000	\$190,000
Earthwork		194,000	CY	\$12	\$2,328,000
Clear & Grub		44.0	AC	\$5,000	\$220,000
Engineering (15%)		1	LS	\$382,000	\$382,000
Contract Administration (8%)		1	LS	\$204,000	\$204,000
Environmental / Permits (5%)		1	LS	\$127,000	\$127,000
Contingency (20%)		1	LS	\$510,000	\$510,000
Total Pond 3					\$3,961,000

5 REFERENCES

Airfield Development Engineering Consultant, Preliminary Report No. 8, Phase 2 and 3 Water Circulation, Sedimentation, and Water Quality Studies, prepared for San Francisco International Airport.

Federal Register, 44CFR65, Title 44--Emergency Management and Assistance, Chapter I--Federal Emergency Management Agency, Department Of Homeland Security, Part 65--Identification and Mapping Of Special Hazard Areas

FEMA Flood Insurance Study, Cities of San Jose, Palo Alto, Mountain View, Milpitas, Sunnyvale, East Palo Alto, Menlo Park, Newark, Fremont, Union City, Hayward; unincorporated areas of Santa Clara County, San Mateo County, and Alameda County; Study Dates: 1997, 1998, 1999

Life Science!, June 2003, South Bay Salt Ponds Initial Stewardship Plan, prepared for U.S. Fish and Wildlife Service and California Department of Fish and Game.

Moffatt & Nichol Engineers 2003, Inventory of Water Conveyance Facilities, South Bay Salt Pond Restoration Project, Prepared for the California State Coastal Conservancy

MT-2, Application Forms and Instructions for Conditional Letters of map Revision and Letters of Map Revision, FEMA Form 81-89 Series, p.1, http://www.fema.gov/fhm/dl_mt-2.shtm

National Research Council, 2000, Risk Analysis and Uncertainty in Flood Damage Reduction Studies

Santa Clara Valley Water District, June 2002, Engineer's Report and Final Environmental Impact Report, Lower Guadalupe River Planning Study, prepared by CH2M Hill.

Siegel, S.W. & P.A.M. Bachand 2002, Feasibility Analysis of South Bay Salt Pond Restoration, San Francisco Estuary, California.

U.S. Army Corps of Engineers 1988 San Francisco Bay Shoreline Study, Southern Alameda and Santa Clara Counties, Appendix C, October 1988

U.S. Army Corps of Engineers 1995, Earthquake Design And Evaluation For Civil Works Projects

U.S. Army Corps of Engineers 1996, Engineering and Design - Risk-Based Analysis for Flood Damage Reduction Studies

U.S. Army Corps of Engineers 2000, Design and Construction of Levees", EM 1110-2-1913, US Army Corps of Engineers, April 30, 2000

U.S. Army Corps of Engineers, 1984 San Francisco District, October 1984, San Francisco Bay Tidal Stage vs. Frequency Study.

U.S. Environmental Protection Agency, San Francisco, California / S. F. Regional Water Quality Control Board, Oakland, California, Goals Project 1999, Baylands Ecosystem Habitat Goals

URS, August 2002, Alameda Creek Levee Reconfiguration Project, Parts I and II



Salt Pond
Restoration Project
LEVEE EVALUATION



Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee
- Reference Line

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 1.1a





Salt Pond
Restoration Project

LEVEE EVALUATION




Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee
- Reference Line

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 1.1b





Salt Pond
Restoration Project

LEVEE EVALUATION



Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee
- Reference Line

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 1.1c





Salt Pond
Restoration Project

LEVEE EVALUATION




Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee
- Reference Line

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 1-1d





Salt Pond
Restoration Project
LEVEE EVALUATION





Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee
- Reference Line

Aerial Photo Source: USGS
Bay Area Regional Database
Date: July 1993


Figure 1.1e






US ARMY CORPS OF ENGINEERS
FREEBOARD REQUIREMENTS

LEEVE CERTIFICATION DECISION TREE



FEMA Criteria = 1% chance median annual flood event plus three feet of freeboard
Reliability = % chance non-exceedance given the 1% chance annual event occurs

Source: "Risk Analysis and Uncertainty in Flood Damage Reduction Studies"



FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA)
FREEBOARD REQUIREMENTS



Salt Pond
Restoration Project

LEVEE EVALUATION




Legend

- Soil Boring Location
- ✦ Cone Penetration Test (CPT) Location

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.2.2a

GRAPHIC SCALE





Salt Pond
Restoration Project
LEVEE EVALUATION




Legend

- Soil Boring Location
- ✦ Cone Penetration Test (CPT) Location

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.2.2b





Salt Pond
Restoration Project

LEVEE EVALUATION





Legend

- Soil Boring Location
- ⊕ Cone Penetration Test (CPT) Location

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.2.2c





Map showing equal lines of land subsidence (in feet) in Santa Clara Valley from 1934 to 1967 (from Poland and Ireland, 1968) overlaid onto topographic mapping from the USGS. Guadalupe River is highlighted in blue.

Figure 3.2.3a

(Source: Lower Guadalupe River Planning Study, SCVWD, 2002)

Map Showing Equal Lines of Land Subsidence in Santa Clara Valley (1934-1967)
Lower Guadalupe River Project

Source: NHC, 2000.

CH2MHILL




Figure 3.2.3b
(Source: Lower Guadalupe River
Planning Study, SCVWD, 2002)

Source: Atwater, B.F., Hedel, C.W., and Heeley, E.J., "Late Quaternary depositional history, Holocene sea-level changes, and vertical crustal movement, southern San Francisco Bay, CA," Geological Survey Professional Paper 1014, 15p.

Northwest Hydraulic Consultants, 2000. Lower Guadalupe River Sedimentation Study, Santa Clara Valley Water District.

Land Subsidence and Depth to Water Table in San Jose (1906-1995) Lower Guadalupe River Project





Salt Pond
Restoration Project

LEVEE EVALUATION





Legend

-  FEMA Special Flood Hazard Area
-  Tide Gage

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.3.1a






Salt Pond
Restoration Project
LEVEE EVALUATION




Legend

-  FEMA Special Flood Hazard Area
-  Tide Gage

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.3.1b





Salt Pond
Restoration Project

LEVEE EVALUATION




Legend


- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991


Figure 3.3.2a

GRAPHIC SCALE





POND A1



Salt Pond
Restoration Project

LEVEE EVALUATION




Legend


- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.3.2c

GRAPHIC SCALE





STATION 20+00±
LOOKING EAST

POND A2W



Salt Pond
Restoration Project

LEVEE EVALUATION




Legend


- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.3.2e


GRAPHIC SCALE





STATION 45+00±
LOOKING SOUTHEAST

POND A2E



Salt Pond
Restoration Project
LEVEE EVALUATION




Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.3.2g





POND A3W



Salt Pond
Restoration Project
LEVEE EVALUATION





Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.3.2i





Salt Pond
Restoration Project
LEVEE EVALUATION







Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.3.2j





POND A4

Photos: Bay Trail Guided Photo Tour
www.abag.ca.gov/bayarea/baytrail/vtour/map3/access/Syvlblds/syvlblds1.htm


Salt Pond Restoration Project
 LEVEE EVALUATION

Figure 3.3.2k

MOFFATT & NICHOL
 ENGINEERS
 WALNUT CREEK, CALIFORNIA



Salt Pond
Restoration Project
LEVEE EVALUATION




Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.3.2f





Salt Pond
Restoration Project

LEVEE EVALUATION





Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee


Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.3.2m





Salt Pond
Restoration Project
LEVEE EVALUATION




Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.3.2n



Town Of
Alviso

Existing Levee

New Chicago
Marsh Pond



Note: Reference Line location does
not appear in photo.

STATION 56+00±
LOOKING NORTH

New Chicago
Marsh Pond

Reference Line at
Existing Levee Crest

Town Of
Alviso



STATION 47+00±
LOOKING EAST

NEW CHICAGO MARSH

Salt Pond Restoration Project
LEVEE EVALUATION

Figure 3.3.2o

MOFFATT & NICHOL
ENGINEERS
WALNUT CREEK, CALIFORNIA



Salt Pond
Restoration Project

LEVEE EVALUATION




Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.3.2p





STATION 30+00±
LOOKING NORTH

POND A22



Salt Pond
Restoration Project

LEVEE EVALUATION





Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991


Figure 3.4.2a





Note: The portion of pond shown in the section was dry at the time of investigation.

TYPICAL SECTION
LOOKING EAST



STATION 14+00±
LOOKING EAST

WEST BAY POND S5



Salt Pond
Restoration Project
LEVEE EVALUATION




Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.4.2c





TYPICAL SECTION
LOOKING WEST




STATION 48+00±
LOOKING WEST

WEST BAY POND 3



Salt Pond
Restoration Project
LEVEE EVALUATION





Legend

- Existing Bay Trail
- Existing Salt Pond Levee
- Existing Publicly-Maintained Levee

Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.4.2e






Salt Pond
Restoration Project

LEVEE EVALUATION



Legend


 FEMA Special
Flood Hazard
Area

 Tide Gage


Aerial Photo Source: USGS
Bay Area Regional Database
Date: Oct 1991

Figure 3.4.1

GRAPHIC SCALE



Y:\AlamedaCreek\MXD_Report\Fig 13 100 Year Floodplain_dwg_080902.mxd



Legend		
100 Year Flood Depths (ft)		Regional Elevations
0-0.5	2.5-3.0	5.5-6.0
0.5-1.0	3.0-3.5	6.0-6.5
1.0-1.5	3.5-4.0	6.5-7.0
1.5-2.0	4.0-4.5	7.0-7.5
2.0-2.5	4.5-5.0	7.5-8.0
	5.0-5.5	8.0-14.0
		High: 382.3 ft.
		Low: -49 ft.

Elevation data derived from LIDAR topographic survey, 2001
Datum: NAD 1983
Projection: State Plane, California Zone III
Units: Meters
Vertical Datum: NGVD 1929





Figure 3.5.1: 100 – Year Floodplain
(Source: Alameda Creek Floodplain Study,
URS, 2003, Prepared for ACFCWCD)



Legend

- Fabridams
- + Stations - 1,000 ft. Interval
- + Station - 10,000 ft. Interval
- ✱ Erosion control Sills
- Flood Control Channel


0 2,000 4,000 6,000 8,000 10,000 12,000 Feet




URS

Figure 3.5.2a: Site Features
(Source: Alameda Creek Floodplain Study, URS, 2003, Prepared for ACFCWCD)


Figure 8 Comparison of LIDAR Survey and County In-Channel Survey at Selected Cross Sections





Crest Elev. (ft)	Slope H : V	Factor of Safety for Slope Stability						Settlement (feet)		
		Strength = 200 (psf)			Strength = 400 (psf)					
		Bay Mud Thickness			Bay Mud Thickness			Bay Mud Thickness		
		5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)
15.5	3 : 1	< 1.0	< 1.0	< 1.0	1.8	1.6	1.4			
14.5	8 : 1	1.7	1.3	1.1	3.3	2.7	2.3			
12.0	3 : 1	1.2	1.0	< 1.0	2.4	2.0	1.9			
12.0	8 : 1	1.9	1.5	1.3	3.9	3.0	2.7			

SCALE



1 inch = 20 feet


Station 0+00 - 6+00 (Way Point 76)
South Bay Salt Ponds
Alviso, California

Cross-Section

Hultaren - Tillis Engineers


Project No. 561-01

Figure 4.3.3a



Crest Elev. (ft)	Slope H : V	Factor of Safety for Slope Stability						Settlement (feet)		
		Strength = 200 (psf)			Strength = 400 (psf)					
		Bay Mud Thickness			Bay Mud Thickness			Bay Mud Thickness		
		5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)
15.5	3 : 1	< 1.0	< 1.0	< 1.0	1.7	1.4	1.4	1	1	1
14.5	8 : 1	1.5	1.2	1.0	3.0	2.5	2.1	< 1	1	1
12.0	3 : 1	1.0	< 1.0	< 1.0	2.1	1.8	1.7	< 1	1	1
12.0	8 : 1	1.8	1.4	1.2	3.6	2.8	2.5	< 1	1	1

SCALE



1 inch = 20 feet


Station 6+00 - 10+00 (Way Point 77)
South Bay Salt Ponds
Alviso, California

Cross-Section

Hultaren - Tillis Engineers


Project No. 561 01

Figure 4.3.3b



Crest Elev. (ft)	Slope H : V	Factor of Safety for Slope Stability						Settlement (feet)		
		Strength = 200 (psf)			Strength = 400 (psf)					
		Bay Mud Thickness			Bay Mud Thickness			Bay Mud Thickness		
		5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)
15.5	3 : 1	< 1.0	< 1.0	< 1.0	1.8	1.5	1.4	1	3	4
14.5	8 : 1	1.5	1.2	1.1	3.1	2.5	2.2	1	2	3
12.0	3 : 1	1.1	< 1.0	< 1.0	2.2	1.9	1.7	1	2	3
12.0	8 : 1	1.8	1.4	1.3	2.6	2.9	2.6	1	2	3

SCALE



1 inch = 20 feet


Station 15+00 - 43+00 (Way Point 78)
South Bay Salt Ponds
Alviso, California

Cross-Section

Hultaren - Tillis Engineers


Project No. 561 01

Figure 4.3.3c



Crest Elev. (ft)	Slope H : V	Factor of Safety for Slope Stability						Settlement (feet)		
		Strength = 200 (psf)			Strength = 400 (psf)					
		Bay Mud Thickness			Bay Mud Thickness			Bay Mud Thickness		
		5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)
15.5	3 : 1	< 1.0	< 1.0	< 1.0	1.7	1.4	1.4	2	3	5
14.5	8 : 1	1.5	1.2	1.0	3.0	2.4	2.0	2	3	4
12.0	3 : 1	1.0	< 1.0	< 1.0	2.0	1.8	1.7	2	3	4
12.0	8 : 1	1.7	1.3	1.2	3.4	2.7	2.5	2	3	4

SCALE



1 inch = 20 feet


Station 0+00 - 37+00 (Way Point 80)
South Bay Salt Ponds
Alviso, California

Cross-Section

Hultaren - Tillis Engineers


Project No. 561 01

Figure 4.3.3d



Crest Elev. (ft)	Slope H : V	Factor of Safety for Slope Stability						Settlement (feet)		
		Strength = 200 (psf)			Strength = 400 (psf)					
		Bay Mud Thickness			Bay Mud Thickness			Bay Mud Thickness		
		5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)
15.5	3 : 1	< 1.0	< 1.0	< 1.0	1.4	1.1	1.0	2	3	5
14.5	8 : 1	1.2	1.0	< 1.0	2.5	2.0	1.5	2	3	5
12.0	3 : 1	< 1.0	< 1.0	< 1.0	1.6	1.4	1.3	2	3	4
12.0	8 : 1	1.4	1.1	< 1.0	2.8	2.2	1.8	2	3	4

SCALE



1 inch = 20 feet

Station 38+00 - 48+00 (Way Point 81)
South Bay Salt Ponds
Alviso, California

Cross-Section

Hultaren - Tillis Engineers


Project No. 561 01

Figure 4.3.3e



Crest Elev. (ft)	Slope H : V	Factor of Safety for Slope Stability						Settlement (feet)		
		Strength = 200 (psf)			Strength = 400 (psf)					
		Bay Mud Thickness			Bay Mud Thickness			Bay Mud Thickness		
		5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)
15.5	3 : 1	< 1.0	< 1.0	< 1.0	1.6	1.4	1.3	1	2	3
14.5	8 : 1	1.4	1.2	<1.0	2.9	2.4	2.0	1	2	3
12.0	3 : 1	< 1.0	< 1.0	< 1.0	1.9	1.7	1.6	1	2	2
12.0	8 : 1	1.7	1.3	1.1	3.3	2.7	2.3	1	2	2

SCALE



1 inch = 20 feet


Station 0+00 - 17+00 (Way Point 82)
South Bay Salt Ponds
Alviso, California

Cross-Section

Hultaren - Tillis Engineers


Project No. 561 01

Figure 4.3.3f



Crest Elev. (ft)	Slope H : V	Factor of Safety for Slope Stability						Settlement (feet)		
		Strength = 200 (psf)			Strength = 400 (psf)					
		Bay Mud Thickness			Bay Mud Thickness			Bay Mud Thickness		
		5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)
15.5	3 : 1	< 1.0	< 1.0	< 1.0	1.5	1.3	1.2	2	3	5
14.5	8 : 1	1.4	1.1	<1.0	2.8	2.2	1.8	2	3	5
12.0	3 : 1	< 1.0	< 1.0	< 1.0	1.8	1.6	1.4	2	3	4
12.0	8 : 1	1.5	1.2	1.1	3.1	2.5	2.2	2	3	4

SCALE



1 inch = 20 feet


Station 17+00 - 41+00 (Way Point 83)
South Bay Salt Ponds
Alviso, California

Cross-Section

Hultaren - Tillis Engineers

Project No. 561-01

Figure 4.3.3a



Crest Elev. (ft)	Slope H : V	Factor of Safety for Slope Stability						Settlement (feet)		
		Strength = 200 (psf)			Strength = 400 (psf)					
		Bay Mud Thickness			Bay Mud Thickness			Bay Mud Thickness		
		5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)
15.5	3 : 1	< 1.0	< 1.0	< 1.0	1.5	1.3	1.2	2	3	5
14.5	8 : 1	1.4	1.1	<1.0	2.8	2.2	1.8	2	3	5
12.0	3 : 1	< 1.0	< 1.0	< 1.0	1.8	1.5	1.5	2	3	4
12.0	8 : 1	1.6	1.2	1.1	3.2	2.5	2.2	2	3	4

SCALE



1 inch = 20 feet


Station 41+00 - 62+00 (Way Point 84)
South Bay Salt Ponds
Alviso, California

Cross-Section

Hultaren - Tillis Engineers

Project No. 561 01

Figure 4.3.3h



Crest Elev. (ft)	Slope H : V	Factor of Safety for Slope Stability						Settlement (feet)		
		Strength = 200 (psf)			Strength = 400 (psf)					
		Bay Mud Thickness			Bay Mud Thickness			Bay Mud Thickness		
		5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)
15.5	3 : 1	< 1.0	< 1.0	< 1.0	1.5	1.3	1.2	2	3	5
14.5	8 : 1	1.4	1.1	<1.0	2.8	2.2	1.8	2	3	5
12.0	3 : 1	< 1.0	< 1.0	< 1.0	1.8	1.6	1.4	2	3	4
12.0	8 : 1	1.5	1.2	1.1	3.1	2.5	2.2	2	3	4

SCALE



1 inch = 20 feet


Station 70+00 - 94+00 (Way Point 86)
South Bay Salt Ponds
Alviso, California

Cross-Section

Hultaren - Tillis Engineers


Project No. 561 01

Figure 4.3.3i



Crest Elev. (ft)	Slope H : V	Factor of Safety for Slope Stability						Settlement (feet)		
		Strength = 200 (psf)			Strength = 400 (psf)					
		Bay Mud Thickness			Bay Mud Thickness			Bay Mud Thickness		
		5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)
15.5	3 : 1	< 1.0	< 1.0	< 1.0	1.6	1.3	1.2	2	3	5
14.5	8 : 1	1.4	1.2	<1.0	2.8	2.3	1.9	2	3	5
12.0	3 : 1	< 1.0	< 1.0	< 1.0	1.9	1.7	1.6	2	3	4
12.0	8 : 1	1.7	1.3	1.1	3.3	2.7	2.3	2	3	4

SCALE



1 inch = 20 feet


Station 94+00 - 110+00 (Way Point 87)
South Bay Salt Ponds
Alviso, California

Cross-Section

Hultaren - Tillis Engineers


Project No. 561 01

Figure 4.3.3i



Crest Elev. (ft)	Slope H : V	Factor of Safety for Slope Stability						Settlement (feet)		
		Strength = 200 (psf)			Strength = 400 (psf)					
		Bay Mud Thickness			Bay Mud Thickness			Bay Mud Thickness		
		5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)
15.5	3 : 1	< 1.0	< 1.0	< 1.0	1.9	1.7	1.6	2	3	4
14.5	8 : 1	1.8	1.4	1.2	3.6	2.8	2.5	2	3	4
12.0	3 : 1	1.3	1.2	1.1	2.7	2.4	2.3	1	3	4
12.0	8 : 1	2.2	1.7	1.4	> 4.0	3.3	2.9	1	3	4

SCALE



1 inch = 20 feet


Station 4+00 - 30+00 (Way Point 89)
South Bay Salt Ponds
West Bay, California

Cross-Section

Hultaren - Tillis Engineers


Project No. 561 01

Figure 4.3.3k



Crest Elev. (ft)	Slope H : V	Factor of Safety for Slope Stability						Settlement (feet)		
		Strength = 200 (psf)			Strength = 400 (psf)					
		Bay Mud Thickness			Bay Mud Thickness			Bay Mud Thickness		
		5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)
15.5	3 : 1	< 1.0	< 1.0	< 1.0	1.9	1.7	1.6	1	1	2
14.5	8 : 1	1.8	1.4	1.2	3.6	2.8	2.5	1	1	2
12.0	3 : 1	1.3	1.2	1.1	2.7	2.4	2.3	< 1	1	1
12.0	8 : 1	2.2	1.7	1.4	> 4.0	3.3	2.9	< 1	1	1

SCALE



1 inch = 20 feet


Station 30+00 - 70+00 (Way Point 91)
South Bay Salt Ponds
West Bay, California

Cross-Section

Hultaren - Tillis Engineers


Project No. 561 01

Figure 4.3.3I



Crest Elev. (ft)	Slope H : V	Factor of Safety for Slope Stability						Settlement (feet)		
		Strength = 200 (psf)			Strength = 400 (psf)					
		Bay Mud Thickness			Bay Mud Thickness			Bay Mud Thickness		
		5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)	5.0 (ft)	10.0 (ft)	15.0 (ft)
15.5	3 : 1	< 1.0	< 1.0	< 1.0	1.9	1.7	1.6	1	2	3
14.5	8 : 1	1.7	1.3	1.2	3.4	2.7	2.5	1	2	3
12.0	3 : 1	1.2	1.1	1.1	2.5	2.3	2.1	1	1	2
12.0	8 : 1	2.0	1.6	1.4	4.0	3.3	2.8	1	1	2

SCALE



1 inch = 20 feet



Station 110+00 - 118+00 (Way Point 92)
South Bay Salt Ponds
West Bay, California

Cross-Section

Hultaren - Tillis Engineers



Project No. 561 01

Figure 4.3.3m




South Bay Salt Ponds
Alviso, California

Stability Analysis Charts
Shear Strength, C = 200 psf




South Bay Salt Ponds
Alviso, California


Stability Analysis Charts
Shear Strength, C = 400 psf




ALVISO COMPLEX - POND A1
PROPOSED TYPICAL SECTION




ALVISO COMPLEX - POND A2W
PROPOSED TYPICAL SECTION




ALVISO COMPLEX - POND A2E
PROPOSED TYPICAL SECTION



ALVISO COMPLEX - POND A3W
PROPOSED TYPICAL SECTION



WEST BAY COMPLEX - POND S5
PROPOSED TYPICAL SECTION




WEST BAY COMPLEX - POND 3
PROPOSED TYPICAL SECTION

APPENDICES

A. Survey Data



- Notes:
1. Elevations shown are in Feet, relative to NGVD 1929.
 2. Waypoints shown are locations where cross-sections were measured (visual reconnaissance level).
 3. GPS Survey performed by Tucker & Associates, Jan 2004.
 4. Additional benchmarks established on site, not shown on Figure.





- Notes:
- 1. Elevations shown are in Feet, relative to NGVD 1929.
 - 2. Waypoints shown are locations where cross-sections were measured (visual reconnaissance level).
 - 3. GPS Survey performed by Tucker & Associates, Jan 2004.
 - 4. Additional benchmarks established on site, not shown on Figure.




Salt Pond
Restoration Project

LEVEE EVALUATION

Alviso Complex (East)




- Notes:
- 1. Elevations shown are in Feet, relative to NGVD 1929.
 - 2. Waypoints shown are locations where cross-sections were measured (visual reconnaissance level).
 - 3. GPS Survey performed by Tucker & Associates, Jan 2004.
 - 4. Additional benchmarks established on site, not shown on Figure.



Salt Pond
Restoration Project
LEVEE EVALUATION





- Notes:
1. Elevations shown are in Feet, relative to NGVD 1929.
 2. Waypoints shown are locations where cross-sections were measured (visual reconnaissance level).
 3. GPS Survey performed by Tucker & Associates, Jan 2004.
 4. Additional benchmarks established on site, not shown on Figure.

B. Field Data Forms

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"023"
Latitude	37.487784
Longitude	-121.959286
Pond Name	
Station from	
Station to	
Crest Elev	
Crest Width	
Crest Condition	
Pond Side Slope	
Inclination	
Pond Side Crest Height	
Pond Side Slope Erosion	
Pond Side Slope	
Vegetation	
Pond Side Toe Condition	
Pond Side Ditch	
Land Side Slope	
Inclination	
Land Side Crest Height	
Land Side Slope Erosion	
Land Side Slope	
Vegetation	
Land Side Toe Condition	
Land Side Ditch	
Levee Material	
Seepage	
Photos Back-Station	
Photos Up-Station	
Comments	Gate

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"024"
Latitude	37.487528
Longitude	-121.964382
Pond Name	
Station from	64+00
Station to	78+00
Crest Elev	
Crest Width	12'
Crest Condition	grasses
Pond Side Slope	19 degrees
Inclination	
Pond Side Crest Height	4'
Pond Side Slope Erosion	minimal
Pond Side Slope	
Vegetation	grasses
Pond Side Toe Condition	12' wide bench
Pond Side Ditch	20' wide, 2' deep, mud
Land Side Slope	20 degrees
Inclination	
Land Side Crest Height	5'
Land Side Slope Erosion	minimal
Land Side Slope	
Vegetation	grasses
Land Side Toe Condition	ditch at toe
Land Side Ditch	8' wide, 3' deep, grass & pickleweed, .5' to 1' vertical face adjacent to levee, remnant fence on far side of ditch
Levee Material	probable Bay Mud
Seepage	none
Photos Back-Station	131, 133
Photos Up-Station	132, 134
Comments	4" diameter active burrows in levee crest

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"030"
Latitude	37.484911
Longitude	-121.964388
Pond Name	
Station from	54+00
Station to	63+00
Crest Elev	
Crest Width	
Crest Condition	
Pond Side Slope Inclination	
Pond Side Crest Height	3'
Pond Side Slope Erosion	
Pond Side Slope Vegetation	
Pond Side Toe Condition	
Pond Side Ditch	
Land Side Slope Inclination	
Land Side Crest Height	
Land Side Slope Erosion	
Land Side Slope Vegetation	
Land Side Toe Condition	
Land Side Ditch	
Levee Material	
Seepage	
Photos Back-Station	
Photos Up-Station	
Comments	fill extends into pond 75' bet Sta 52+00 and 54+00, no ditch on pond side over this range, levee crest width down to 6' in some areas

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"031"
Latitude	37.482444
Longitude	-121.965620
Pond Name	
Station from	
Station to	
Crest Elev	
Crest Width	
Crest Condition	
Pond Side Slope Inclination	
Pond Side Crest Height	
Pond Side Slope Erosion	
Pond Side Slope Vegetation	
Pond Side Toe Condition	
Pond Side Ditch	
Land Side Slope Inclination	
Land Side Crest Height	
Land Side Slope Erosion	
Land Side Slope Vegetation	
Land Side Toe Condition	
Land Side Ditch	
Levee Material	
Seepage	
Photos Back-Station	
Photos Up-Station	
Comments	end of slump area between Gate and this Way Point, approx. 1' below balance of levee further to the north, levee paved w/gravel

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"032"
Latitude	37.482461
Longitude	-121.966869
Pond Name	A22
Station from	32+00
Station to	45+00
Crest Elev	
Crest Width	15'
Crest Condition	3/8"-gravel
Pond Side Slope	65 degrees
Inclination	
Pond Side Crest Height	3'
Pond Side Slope Erosion	heavy
Pond Side Slope Vegetation	sparse (eroding)
Pond Side Toe Condition	5 degrees to ditch
Pond Side Ditch	20' from toe
Land Side Slope	42 degrees
Inclination	
Land Side Crest Height	3'
Land Side Slope Erosion	moderate w/6' scarp
Land Side Slope Vegetation	grasses w/some pickleweed
Land Side Toe Condition	ditch at toe
Land Side Ditch	6' wide x 1' deep
Levee Material	Sandy Silt
Seepage	no signs
Photos Back-Station	138, 139
Photos Up-Station	140, 141
Comments	

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"033"
Latitude	37.481539
Longitude	-121.969094
Pond Name	A22
Station from	25+00
Station to	31+00
Crest Elev	
Crest Width	16'
Crest Condition	3/8"-gravel
Pond Side Slope	40 degrees
Inclination	
Pond Side Crest Height	3'
Pond Side Slope Erosion	moderate to heavy
Pond Side Slope Vegetation	sparse/eroded
Pond Side Toe Condition	Silty Sand, 5 degrees to ditch
Pond Side Ditch	15' from toe, 15' wide ditch
Land Side Slope	34 degrees
Inclination	
Land Side Crest Height	3'
Land Side Slope Erosion	minimal
Land Side Slope Vegetation	grasses/pickleweed
Land Side Toe Condition	ditch at toe
Land Side Ditch	6' wide, 1' deep
Levee Material	Sandy Silt
Seepage	None
Photos Back-Station	142, 143
Photos Up-Station	144, 145
Comments	

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"035"
Latitude	37.480591
Longitude	-121.970668
Pond Name	A22
Station from	13+00
Station to	25+00
Crest Elev	
Crest Width	20'
Crest Condition	3/8"-gravel
Pond Side Slope	26 degrees
Inclination	
Pond Side Crest Height	3'
Pond Side Slope Erosion	minimal
Pond Side Slope Vegetation	minimal
Pond Side Toe Condition	5 degrees, barren
Pond Side Ditch	20' to ditch, 15' wide
Land Side Slope	24 degrees
Inclination	
Land Side Crest Height	2'
Land Side Slope Erosion	minimal
Land Side Slope Vegetation	grasses/pickleweed
Land Side Toe Condition	ditch at toe
Land Side Ditch	8' wide, 2' deep
Levee Material	Sandy Silt
Seepage	None
Photos Back-Station	146, 147
Photos Up-Station	148, 149
Comments	access ramp into pond @ WP34 (photo 148)

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"038"
Latitude	37.478225
Longitude	-121.973122
Pond Name	A22
Station from	0+00
Station to	13+00
Crest Elev	
Crest Width	15'
Crest Condition	3/8"-gravel
Pond Side Slope	34 degrees
Inclination	
Pond Side Crest Height	3'
Pond Side Slope Erosion	heavy (wind wave)
Pond Side Slope Vegetation	none
Pond Side Toe Condition	5 degrees to ditch
Pond Side Ditch	8' to toe, standing water
Land Side Slope	35 degrees
Inclination	
Land Side Crest Height	3'
Land Side Slope Erosion	minimal
Land Side Slope Vegetation	pickleweed
Land Side Toe Condition	tidal slough at toe
Land Side Ditch	tidal slough, 8-10' wide
Levee Material	Sandy Silt
Seepage	none
Photos Back-Station	155, 156
Photos Up-Station	157, 158
Comments	Splash berm on pond side

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"040"
Latitude	37.429621
Longitude	-121.978502
Pond Name	
Station from	8+00
Station to	
Crest Elev	
Crest Width	
Crest Condition	
Pond Side Slope Inclination	
Pond Side Crest Height	
Pond Side Slope Erosion	
Pond Side Slope Vegetation	
Pond Side Toe Condition	
Pond Side Ditch	
Land Side Slope Inclination	
Land Side Crest Height	
Land Side Slope Erosion	
Land Side Slope Vegetation	
Land Side Toe Condition	
Land Side Ditch	
Levee Material	
Seepage	
Photos Back-Station	Pan [159-167]
Photos Up-Station	
Comments	

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"041"
Latitude	37.429240
Longitude	-121.980614
Pond Name	
Station from	~0+00
Station to	
Crest Elev	
Crest Width	
Crest Condition	
Pond Side Slope Inclination	
Pond Side Crest Height	
Pond Side Slope Erosion	
Pond Side Slope Vegetation	
Pond Side Toe Condition	
Pond Side Ditch	
Land Side Slope Inclination	
Land Side Crest Height	
Land Side Slope Erosion	
Land Side Slope Vegetation	
Land Side Toe Condition	
Land Side Ditch	
Levee Material	
Seepage	
Photos Back-Station	
Photos Up-Station	168 and 169
Comments	Approx. location of intersection with existing Flood Control levee

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"043"
Latitude	37.427529
Longitude	-121.975382
Pond Name	
Station from	North of Catherine St.
Station to	between Gold & State/Liberty
Crest Elev	High fill ground to the east, low to the west
Crest Width	
Crest Condition	storm drain crosses here
Pond Side Slope	
Inclination	
Pond Side Crest Height	
Pond Side Slope Erosion	
Pond Side Slope Vegetation	
Pond Side Toe Condition	
Pond Side Ditch	
Land Side Slope	
Inclination	
Land Side Crest Height	
Land Side Slope Erosion	
Land Side Slope Vegetation	
Land Side Toe Condition	
Land Side Ditch	
Levee Material	
Seepage	
Photos Back-Station	170 to 174
Photos Up-Station	
Comments	

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"044"
Latitude	37.432484
Longitude	-121.970246
Pond Name	
Station from	State and Pacific (N End)
Station to	
Crest Elev	
Crest Width	
Crest Condition	
Pond Side Slope	
Inclination	
Pond Side Crest Height	
Pond Side Slope Erosion	
Pond Side Slope Vegetation	
Pond Side Toe Condition	
Pond Side Ditch	
Land Side Slope	
Inclination	
Land Side Crest Height	
Land Side Slope Erosion	
Land Side Slope Vegetation	
Land Side Toe Condition	
Land Side Ditch	
Levee Material	
Seepage	
Photos Back-Station	175-178
Photos Up-Station	
Comments	

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"045"
Latitude	37.432839
Longitude	-121.966698
Pond Name	
Station from	State at Spreckels
Station to	83+00
Crest Elev	
Crest Width	
Crest Condition	asphalt road
Pond Side Slope	19 degrees towards marsh
Inclination	
Pond Side Crest Height	
Pond Side Slope Erosion	minimal
Pond Side Slope Vegetation	grasses
Pond Side Toe Condition	
Pond Side Ditch	none (marsh)
Land Side Slope	
Inclination	
Land Side Crest Height	
Land Side Slope Erosion	
Land Side Slope Vegetation	
Land Side Toe Condition	
Land Side Ditch	
Levee Material	
Seepage	
Photos Back-Station	179-180
Photos Up-Station	
Comments	

Alviso Pond Complex
Site Visit November 20, 2003

Date	11/20/2003
Persons	Ed and Dilip
Way Point No.	"046"
Latitude	37.417048
Longitude	-121.987065
Pond Name	
Station from	Pond #85
Station to	Guadalupe St. at San Tomas Aquino Ct.
Crest Elev	
Crest Width	
Crest Condition	
Pond Side Slope	
Inclination	
Pond Side Crest Height	
Pond Side Slope Erosion	
Pond Side Slope Vegetation	
Pond Side Toe Condition	
Pond Side Ditch	
Land Side Slope	
Inclination	
Land Side Crest Height	
Land Side Slope Erosion	
Land Side Slope Vegetation	
Land Side Toe Condition	
Land Side Ditch	
Levee Material	
Seepage	
Photos Back-Station	181-183
Photos Up-Station	
Comments	

Alviso Pond Complex
Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"076"
Latitude	37.43584
Longitude	-122.09869
Pond Name	Charleston Slough
Station from	
Station to	
Crest Elev	
Crest Width	16'
Crest Condition	paved
Pond Side Slope	11deg
Inclination	
Pond Side Crest Height	6'
Pond Side Slope Erosion	none
Pond Side Slope	some, pickleweed
Vegetation	
Pond Side Toe Condition	pond
Pond Side Ditch	pond
Land Side Slope	14 deg
Inclination	
Land Side Crest Height	13'
Land Side Slope Erosion	none
Land Side Slope	pickleweed
Vegetation	
Land Side Toe Condition	pond
Land Side Ditch	pond
Levee Material	clay
Seepage	none
Photos Back-Station	1
Photos Up-Station	2
Comments	

Alviso Pond Complex
Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"077"
Latitude	37.43506
Longitude	-122.09683
Pond Name	A1
Station from	6+00
Station to	10+00
Crest Elev	
Crest Width	16'
Crest Condition	paved
Pond Side Slope	upper 30': 6 deg
Inclination	lower 25': 10 deg
Pond Side Crest Height	8'
Pond Side Slope Erosion	none
Pond Side Slope	pickleweed
Vegetation	
Pond Side Toe Condition	pond
Pond Side Ditch	pond
Land Side Slope	22 deg
Inclination	
Land Side Crest Height	16'
Land Side Slope Erosion	none
Land Side Slope	marsh
Vegetation	
Land Side Toe Condition	
Land Side Ditch	none
Levee Material	clay
Seepage	none
Photos Back-Station	3, 5, 6
Photos Up-Station	4
Comments	photos 7, 8, 9: pond to southwest

Alviso Pond Complex
Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"078"
Latitude	37.43551
Longitude	-122.09216
Pond Name	A1
Station from	15+00
Station to	44+00
Crest Elev	
Crest Width	25'
Crest Condition	paved, Bay Trail
Pond Side Slope	upper: 25 deg; 30' wide bench
Inclination	lower: 11 deg
Pond Side Crest Height	upper: 13', lower: 3'
Pond Side Slope Erosion	none
Pond Side Slope Vegetation	pickleweed on lower slope
Pond Side Toe Condition	pond
Pond Side Ditch	pond
Land Side Slope	none, landfill
Inclination	
Land Side Crest Height	none, landfill
Land Side Slope Erosion	none, landfill
Land Side Slope Vegetation	none, landfill
Land Side Toe Condition	none, landfill
Land Side Ditch	none
Levee Material	clay
Seepage	none
Photos Back-Station	10
Photos Up-Station	11
Comments	

Alviso Pond Complex
Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"079"
Latitude	37.43479
Longitude	-122.08584
Pond Name	Permanente Creek
Station from	
Station to	
Crest Elev	
Crest Width	
Crest Condition	
Pond Side Slope	
Inclination	
Pond Side Crest Height	
Pond Side Slope Erosion	
Pond Side Slope Vegetation	
Pond Side Toe Condition	
Pond Side Ditch	
Land Side Slope	
Inclination	
Land Side Crest Height	
Land Side Slope Erosion	
Land Side Slope Vegetation	
Land Side Toe Condition	
Land Side Ditch	
Levee Material	
Seepage	
Photos Back-Station	
Photos Up-Station	
Comments	panorama photos 12 to 15

Alviso Pond Complex
Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"080"
Latitude	37.43557
Longitude	-122.07615
Pond Name	A2W
Station from	0+00
Station to	37+00
Crest Elev	
Crest Width	30'
Crest Condition	paved upper, gravel lower
Pond Side Slope	landfill slope 25 deg, 30' bench, near
Inclination	vertical scarp at lower slope
Pond Side Crest Height	14'
Pond Side Slope Erosion	lower slope eroding
Pond Side Slope	none
Vegetation	
Pond Side Toe Condition	pond
Pond Side Ditch	pond
Land Side Slope	landfill
Inclination	
Land Side Crest Height	landfill
Land Side Slope Erosion	landfill
Land Side Slope	landfill
Vegetation	
Land Side Toe Condition	landfill
Land Side Ditch	landfill
Levee Material	clay/some debris
Seepage	none
Photos Back-Station	16
Photos Up-Station	17
Comments	

Alviso Pond Complex
Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"081"
Latitude	37.43568
Longitude	-122.07125
Pond Name	
Station from	38+00
Station to	48+00
Crest Elev	
Crest Width	30' at lower bench
Crest Condition	gravel lower
Pond Side Slope	near vertical at lower, 13 deg at berm
Inclination	
Pond Side Crest Height	bench: 2', berm: 5'
Pond Side Slope Erosion	active
Pond Side Slope	pickleweed on lower, grasses at berm
Vegetation	
Pond Side Toe Condition	pond
Pond Side Ditch	pond
Land Side Slope	8 deg to marsh
Inclination	
Land Side Crest Height	4'
Land Side Slope Erosion	none
Land Side Slope	marsh
Vegetation	
Land Side Toe Condition	none/marsh
Land Side Ditch	none
Levee Material	clay
Seepage	none
Photos Back-Station	18
Photos Up-Station	19
Comments	panorama photos 20-23 (from 19 to 18)

Alviso Pond Complex
Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"082"
Latitude	37.43403
Longitude	-122.06377
Pond Name	A2E
Station from	0+00
Station to	17+00
Crest Elev	
Crest Width	15' + 20' = 35'
Crest Condition	clay, slick, low, cast-up
Pond Side Slope	8 deg
Inclination	
Pond Side Crest Height	3'
Pond Side Slope Erosion	none
Pond Side Slope	barren
Vegetation	
Pond Side Toe Condition	pickleweed, 10' wide, 20:1 slope (cast-up from pond slope)
Pond Side Ditch	none
Land Side Slope	11 deg
Inclination	
Land Side Crest Height	5'
Land Side Slope Erosion	none
Land Side Slope	pickleweed in upper, grass towards
Vegetation	ponded water
Land Side Toe Condition	ponded
Land Side Ditch	ponded
Levee Material	clay
Seepage	none
Photos Back-Station	24
Photos Up-Station	25
Comments	pond on both sides, consider moving FCL behind ponded water

Alviso Pond Complex
Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"083"
Latitude	37.43460
Longitude	-122.05838
Pond Name	A2E
Station from	17+00
Station to	new station line
Crest Elev	
Crest Width	12'
Crest Condition	slick, clay
Pond Side Slope	5 deg, 20' wide side slope
Inclination	
Pond Side Crest Height	3'
Pond Side Slope Erosion	active
Pond Side Slope	pickleweed near toe only
Vegetation	
Pond Side Toe Condition	2' vertical to water
Pond Side Ditch	none visible
Land Side Slope	10 deg
Inclination	
Land Side Crest Height	4'
Land Side Slope Erosion	none visible
Land Side Slope	pickleweed
Vegetation	
Land Side Toe Condition	dessicated mud
Land Side Ditch	none visible
Levee Material	clay
Seepage	none
Photos Back-Station	26
Photos Up-Station	27
Comments	

Alviso Pond Complex
Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"084"
Latitude	37.43431
Longitude	-122.05326
Pond Name	A2E
Station from	
Station to	
Crest Elev	
Crest Width	15'
Crest Condition	slick, clay
Pond Side Slope	10 deg
Inclination	
Pond Side Crest Height	3'
Pond Side Slope Erosion	moderate
Pond Side Slope Vegetation	upper: barren, lower: pickleweed
Pond Side Toe Condition	pond
Pond Side Ditch	none observed
Land Side Slope	13 deg
Inclination	
Land Side Crest Height	4'
Land Side Slope Erosion	none
Land Side Slope Vegetation	pickleweed/grasses
Land Side Toe Condition	mudflat
Land Side Ditch	none
Levee Material	clay
Seepage	none
Photos Back-Station	28
Photos Up-Station	29
Comments	

Alviso Pond Complex
Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"085"
Latitude	37.42740
Longitude	-122.04434
Pond Name	
Station from	
Station to	
Crest Elev	
Crest Width	
Crest Condition	
Pond Side Slope	
Inclination	
Pond Side Crest Height	
Pond Side Slope Erosion	
Pond Side Slope Vegetation	
Pond Side Toe Condition	
Pond Side Ditch	
Land Side Slope	
Inclination	
Land Side Crest Height	
Land Side Slope Erosion	
Land Side Slope Vegetation	
Land Side Toe Condition	
Land Side Ditch	
Levee Material	
Seepage	
Photos Back-Station	
Photos Up-Station	30
Comments	photo of ditches/channels

Alviso Pond Complex
Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"086"
Latitude	37.42756
Longitude	-122.04266
Pond Name	A3W
Station from	70+00
Station to	94+00
Crest Elev	
Crest Width	30'
Crest Condition	trail, compacted clay
Pond Side Slope	16 deg
Inclination	
Pond Side Crest Height	3'
Pond Side Slope Erosion	near vertical
Pond Side Slope	grass
Vegetation	
Pond Side Toe Condition	pond at toe
Pond Side Ditch	none, pond
Land Side Slope	22 deg
Inclination	
Land Side Crest Height	5'
Land Side Slope Erosion	none
Land Side Slope	grassy
Vegetation	
Land Side Toe Condition	2' vertical to water
Land Side Ditch	drainage channel
Levee Material	clay
Seepage	
Photos Back-Station	31
Photos Up-Station	32
Comments	

Alviso Pond Complex
Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"087"
Latitude	37.42730
Longitude	-122.04005
Pond Name	
Station from	94+00
Station to	110+00
Crest Elev	
Crest Width	25'
Crest Condition	trail, compacted clay
Pond Side Slope	vertical
Inclination	
Pond Side Crest Height	4' scarp
Pond Side Slope Erosion	active
Pond Side Slope	none
Vegetation	
Pond Side Toe Condition	pond
Pond Side Ditch	none, pond
Land Side Slope	35 deg
Inclination	
Land Side Crest Height	6'
Land Side Slope Erosion	none/some
Land Side Slope	grasses
Vegetation	
Land Side Toe Condition	drainage channel
Land Side Ditch	drainage channel
Levee Material	clay
Seepage	
Photos Back-Station	33
Photos Up-Station	34, 35
Comments	

Alviso Pond Complex

Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"088"
Latitude	37.43167
Longitude	-122.03053
Pond Name	
Station from	
Station to	
Crest Elev	
Crest Width	10'
Crest Condition	gravel
Pond Side Slope	27 deg
Inclination	
Pond Side Crest Height	6.5'
Pond Side Slope Erosion	none - significant burrowing
Pond Side Slope Vegetation	grasses
Pond Side Toe Condition	20' to waterline, mudflat
Pond Side Ditch	
Land Side Slope	29 deg
Inclination	
Land Side Crest Height	4'
Land Side Slope Erosion	riprap (concrete debris)
Land Side Slope Vegetation	none - riprap
Land Side Toe Condition	oxidation pond
Land Side Ditch	oxidation pond
Levee Material	unknown
Seepage	
Photos Back-Station	36
Photos Up-Station	37
Comments	panorama photos 38 to 41 (from 37 to 36)

West Bay Pond Complex

Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"089"
Latitude	37.48540
Longitude	-122.17195
Pond Name	
Station from	
Station to	
Crest Elev	
Crest Width	6' wide berm, 1' high + 16' wide levee
Crest Condition	
Pond Side Slope	1:15 for 20', then flat
Inclination	
Pond Side Crest Height	3'
Pond Side Slope Erosion	severe, near vertical
Pond Side Slope	bare, eroding
Vegetation	
Pond Side Toe Condition	salt pan/flat
Pond Side Ditch	none
Land Side Slope	32 deg to berm, 36 deg to ditch
Inclination	
Land Side Crest Height	3' bench to crest, 4' water to bench
Land Side Slope Erosion	mild
Land Side Slope	grass
Vegetation	
Land Side Toe Condition	F.C. channel
Land Side Ditch	F.C. channel
Levee Material	clay
Seepage	none
Photos Back-Station	42 pond, 43 channel
Photos Up-Station	44 pond, 45 channel
Comments	

West Bay Pond Complex

Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"090"
Latitude	37.48415
Longitude	-122.16598
Pond Name	
Station from	
Station to	
Crest Elev	
Crest Width	45'
Crest Condition	grass
Pond Side Slope	23 deg
Inclination	
Pond Side Crest Height	2'
Pond Side Slope Erosion	active
Pond Side Slope	bare
Vegetation	
Pond Side Toe Condition	mudflat, 20:1, 25' wide
Pond Side Ditch	pond, 1' deep
Land Side Slope	34 deg
Inclination	
Land Side Crest Height	2'
Land Side Slope Erosion	moderate
Land Side Slope	sparse
Vegetation	
Land Side Toe Condition	mudflat (dried pond)
Land Side Ditch	none
Levee Material	clay
Seepage	none
Photos Back-Station	46 pond, 48 "landside"
Photos Up-Station	47 pond, 49 "landside", panorama 50-55
Comments	possible alternate alignment to create detention basin on "landside"

West Bay Pond Complex

Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"091"
Latitude	37.48266
Longitude	-122.16076
Pond Name	
Station from	
Station to	
Crest Elev	
Crest Width	>50' (~55' to trail)
Crest Condition	
Pond Side Slope	12 deg
Inclination	
Pond Side Crest Height	3'
Pond Side Slope Erosion	moderate
Pond Side Slope	sparse
Vegetation	
Pond Side Toe Condition	8' wide mudflat to channel, 20:1 slope
Pond Side Ditch	none - channel 1' deep, salt on channel edges
Land Side Slope	n/a
Inclination	
Land Side Crest Height	n/a
Land Side Slope Erosion	n/a
Land Side Slope	n/a
Vegetation	
Land Side Toe Condition	n/a
Land Side Ditch	n/a
Levee Material	clay
Seepage	none
Photos Back-Station	56
Photos Up-Station	57
Comments	12" HDPE pipeline along shore, extends to flood slough.

West Bay Pond Complex

Site Visit December 16, 2003

Date	12/16/2003
Persons	Ed and Dilip
Way Point No.	"092"
Latitude	37.48813
Longitude	-122.14269
Pond Name	
Station from	
Station to	
Crest Elev	
Crest Width	20' + berm 8' wide x 1' high
Crest Condition	trail
Pond Side Slope	14 deg
Inclination	
Pond Side Crest Height	4'
Pond Side Slope Erosion	active
Pond Side Slope	none
Vegetation	
Pond Side Toe Condition	12' wide mudflat to channel
Pond Side Ditch	channel
Land Side Slope	41 deg
Inclination	
Land Side Crest Height	4'
Land Side Slope Erosion	none
Land Side Slope	grasses along slope
Vegetation	
Land Side Toe Condition	
Land Side Ditch	Ravenswood Slough
Levee Material	clay
Seepage	none
Photos Back-Station	58 pond, 60 marsh (landside)
Photos Up-Station	59 pond, 61 marsh (landside)
Comments	

C. Pond Elevations

ALVISO PONDS - AREA, ELEVATION, TIDAL PRISM

No	Pond Number	Pond Area (ac)	Pond Elev (NGVD)	Distance to MHHW (ft)	Volume To MHHW (AF)
1	B2	28	0.5	4.2	116
2	B2	108	0.5	4.2	452
3	B2	51	0.5	4.2	214
4	B1	158	-1.3	6.0	945
5	A23	180	1.2	3.0	532
6	A23	275	1.2	3.0	813
7	A22	89	3.0	1.2	104
8	A22	184	3.0	1.2	213
9	A21	142	2.3	1.8	256
10	A20	67	1.8	2.3	156
11	A19	276	1.8	2.4	649
13	A17	136	1.1	3.0	406
14	A16	241	0.6	3.6	856
15	A15	252	0.7	3.4	866
16	A14	351	-0.1	4.8	1,671
17	A13	283	-1.1	5.2	1,470
18	A12	314	-2.0	6.1	1,902
19	A11	268	-1.8	6.5	1,738
20	A10	253	-0.8	5.5	1,402
21	A9	372	0.5	4.2	1,562
22	A8-South	175	-0.5	5.2	912
23	A8	444	-3.4	8.1	3,592
24	A7	269	-0.8	5.5	1,474
25	A5	661	-1.9	6.6	4,391
26	A3W	606	-3.2	7.9	4,780
27	A3N	185	-1.5	6.2	1,140
28	A2W	457	-0.9	5.6	2,566
29	A2E	315	-3.0	7.7	2,424
30	A1	285	-1.9	6.6	1,892
Subtotal		7,425.0			39,496

March 2003 acquisition area only. Ponds A4 and A18 not shown

Source : Siegel & Bachand, 2002

BAUMBERG PONDS - AREA, ELEVATION, TIDAL PRISM

No	Pond Number	Pond Area (ac)	Pond Elev (NGVD)	Distance to MHHW (ft)	Volume To MHHW (AF)
31	1	297	2.2	1.8	541
32	1c	65	3.7	0.3	18
33	2	692	2.1	1.9	1,294
34	2c	32	2.7	1.2	40
35	3c	180	2.9	1.0	187
36	4	202	2.9	1.1	216
37	4c	168	3.2	0.8	138
38	5	172	2.4	1.6	275
39	5c	96	3.0	1.0	99
40	6	183	2.4	1.6	299
41	6a	329	1.1	2.9	957
42	6b	293	1.7	2.3	683
43	6c	85	2.8	1.2	103
44	7	217	2.5	1.5	319
45	8	156	2.8	1.2	192
46	8a	310	4.0	0.0	0
47	8-middle	42	2.8	1.2	52
48	8-north	31	2.8	1.2	39
49	9	386	2.8	1.2	444
50	10	269	2.3	1.6	441
51	11	128	3.0	1.0	124
52	12	117	2.9	1.1	128
53	13	134	3.3	0.7	91
54	14	172	3.7	0.3	46
Subtotal		4,756			6,725

March 2003 acquisition area only.

Source : Siegel & Bachand, 2002

WEST BAY PONDS - AREA, ELEVATION, TIDAL PRISM

ID	Pond Number	Pond Area1 (ac)	Pond Elev2 (NGVD)	Pond Distance to mhhw4 (ft)	Pond Void Space to mhhw5 (AF)
94	1	446	2.0	2.3	1,030
95	2	141	1.9	2.5	346
96	3	296	2.1	2.3	679
97	4	307	2.1	2.2	681
98	5	35	2.5	1.9	67
110	s5	38	2.5	1.6	61
111	sf2	239	2.1	1.9	460
Subtotal		1,503			3,324

March 2003 acquisition area only.

Source : Siegel & Bachand, 2002